

**Contract Documents and Specification for**

**ITB#FY25-021 Gateway Sign and Beautification  
Project at Evans Junction (31<sup>st</sup> St. and Hwy 85)**

**December 18, 2025**

**Tentative Schedule**

<b>Solicitation Advertised</b>	<b>December 18, 2025</b>
<b>Mandatory Pre-Bid Meeting</b>	<b>January 7, 2026</b>
<b>Questions Due</b>	<b>January 9, 2026</b>
<b>Answers Posted to BidNet</b>	<b>January 13, 2026</b>
<b>Solicitation Close &amp; Bid Opening</b>	<b>January 20, 2026</b>
<b>Notice of Intent to Award</b>	<b>January 21, 2026</b>
<b>City Council Approval</b>	<b>February 3, 2026</b>
<b>Notice to Proceed</b>	<b>February 5, 2026</b>

**Dig|Safely.**

## **Table of Contents**

ARTICLE 1	CONTRACTING PROCEDURES
ARTICLE 2	GENERAL CONDITIONS
ARTICLE 3	SPECIAL CONDITIONS
ARTICLE 4	MEASUREMENT AND PAYMENT
ARTICLE 5	VICINITY MAP AND PLAN SET

## ARTICLE 1.0

### CONTRACTING PROCEDURES

#### INDEX

##### CONTENTS

1.1	ADVERTISEMENT FOR BIDS .....	2
1.2	INFORMATION FOR BIDDERS .....	4
1.2.1	OWNER.....	4
1.2.2	ENGINEER.....	4
1.2.3	BID SUBMITTAL.....	4
1.2.4	INFORMALITIES .....	4
1.2.5	CONDITIONS OF WORK .....	4
1.2.6	BID SECURITY.....	5
1.2.7	POWER OF ATTORNEY .....	5
1.2.8	PROJECT SCHEDULE.....	5
1.3	AWARD OF CONTRACT .....	5
1.3.1	CONSIDERATION OF PROPOSALS .....	7
1.3.2	AWARD OF CONTRACT.....	7
1.3.3	CANCELLATION OF AWARD .....	7
1.3.4	EXECUTION AND APPROVAL OF CONTRACT .....	7
1.3.5	FAILURE TO EXECUTE CONTRACT .....	7
1.4	THE CONTRACT: FOLLOWING EXECUTION.....	8
1.4.1	MATERIALS .....	8
1.4.2	PROGRESS SCHEDULE .....	8
1.4.3	ASSIGNMENT OF CONTRACT .....	8
1.4.4	SUBLETTING OF CONTRACT.....	8
1.4.5	OTHER CONTRACTS.....	9
1.5	CONTRACT DOCUMENTS.....	10
1.5.1	NON-COLLUSION STATEMENT .....	10
1.5.2	BID PROPOSAL .....	11
1.5.3	BID SCHEDULE .....	12
1.5.4	BID BOND .....	13
1.5.5	NOTICE OF AWARD .....	14
1.5.6	ACCEPTANCE OF NOTICE .....	14
1.5.7	AGREEMENT .....	15
1.5.8	PERFORMANCE BOND.....	16
1.5.9	PAYMENT BOND .....	19
1.5.10	NOTICE TO PROCEED.....	21
1.5.11	ACCEPTANCE OF NOTICE .....	21
1.5.12	CHANGE ORDER .....	22
1.5.13	NOTICE OF CONTRACTOR'S SETTLEMENT .....	24
1.5.14	FINAL RECEIPT AND GUARANTEE.....	25
1.6	INSURANCE REQUIREMENTS.....	26

## 1.1 ADVERTISEMENT FOR BIDS

The City of Evans, Colorado will receive sealed bids for the following project:

### **Gateway Sign and Beautification Project at Evans Junction (31st Street and Hwy 85)**

**Project Description:** The City of Evans is requesting proposals from qualified contractors for the construction and installation of a Gateway Sign and associated landscaping at the prominent corner of 31st Street and Highway 85, known as **Evans Junction**. This project represents a key component of the City's long-term beautification and corridor enhancement initiative along Hwy 85.

The area encompasses approximately 15 acres of recently improved land, which includes the rerouting of a service road, utility installations for four future commercial pad sites, and the development of Lot 1 by McDonald's Corporation, with an opening in October 2025.

This beautification effort will incorporate the vacated service road east of the site, a detention pond area, and a landscaped entryway to establish a welcoming and attractive gateway to the City.

**Pre-Bid Meeting:** A mandatory pre-bid meeting will be held virtually on **January 7, 2026 at 2:00 p.m. mountain time**. Here is the link to the Teams Meeting. Please try to access the link before the meeting to ensure that it works. If you cannot click directly, please copy and paste into your browser.

[https://teams.microsoft.com/join/19%3ameeting\\_YmlxMjE1MmEtMzkyYy00YTAwLTlkYmQtNDVlOGZjMTEyOTgx%40thread.v2/0?context=%7b%22Tid%22%3a%22e97fcc68-4145-4755-b84b-f31e1eea69a4%22%2c%22Oid%22%3a%22e9a348c6-c706-42c9-9810-b22be862b464%22%7d](https://teams.microsoft.com/join/19%3ameeting_YmlxMjE1MmEtMzkyYy00YTAwLTlkYmQtNDVlOGZjMTEyOTgx%40thread.v2/0?context=%7b%22Tid%22%3a%22e97fcc68-4145-4755-b84b-f31e1eea69a4%22%2c%22Oid%22%3a%22e9a348c6-c706-42c9-9810-b22be862b464%22%7d)

Meeting ID: 233 114 974 577 75  
Passcode: Lf7YH3op

**Bid Submission and Opening:** Bids will be received electronically on BidNet (<http://bidnetdirect.com>) until **2:00 p.m. mountain time** on **January 20, 2026** at which time said bids will be opened and reviewed.

[https://teams.microsoft.com/join/19%3ameeting\\_ZmU3ZTVhNmQtYzNiZi00ZmU1LTk0YjktZWVlYTZjQyOWE4%40thread.v2/0?context=%7b%22Tid%22%3a%22e97fcc68-4145-4755-b84b-f31e1eea69a4%22%2c%22Oid%22%3a%22e9a348c6-c706-42c9-9810-b22be862b464%22%7d](https://teams.microsoft.com/join/19%3ameeting_ZmU3ZTVhNmQtYzNiZi00ZmU1LTk0YjktZWVlYTZjQyOWE4%40thread.v2/0?context=%7b%22Tid%22%3a%22e97fcc68-4145-4755-b84b-f31e1eea69a4%22%2c%22Oid%22%3a%22e9a348c6-c706-42c9-9810-b22be862b464%22%7d)

Meeting ID: 244 270 084 018 99  
Passcode: 3pd9n7px

**Plans and Contract Documents:** Copies of the contract documents may be obtained from the City website or BidNet.

**Bid Bond:** A certified check or bank draft, payable to the City of Evans, Colorado, a satisfactory Bid Bond executed by the Bidder or an acceptable surety in an amount equal to five percent (5%) of the total Bid shall be submitted with each Bid.

Questions concerning the scope of the solicitation should be emailed to Andy Vowell at: [avowell@evanscolorado.gov](mailto:avowell@evanscolorado.gov). Vendors are strongly encouraged to get their questions addressed and answered, as well as clearly understand the City's expectations and procedures.

The City is subject to public information laws, which permit access to most records and documents. Proprietary information in your response must be clearly identified and will be protected to the extent legally permissible. Proposals may not be marked 'Proprietary' in their entirety. Information considered proprietary is limited to material treated as confidential in the normal conduct of business, trade secrets, and discount information. Summary price information may not be designated as proprietary as such information may be carried forward into other public documents. All provisions of any contract resulting from this request for proposal will be public information.

The City reserves the right to reject any or all bids, to waive any informalities in bids, and to accept the bid that is in the best interests of the City of Evans, Colorado.

Andy Vowell  
Procurement and Contract Specialist  
City of Evans  
970-475-2240  
[avowell@evanscolorado.gov](mailto:avowell@evanscolorado.gov)

Published on the City of Evans Website and Rocky Mountain Bid Net on **December 18, 2025.**

## 1.2 INFORMATION FOR BIDDERS

### 1.2.1 OWNER

The OWNER of this project is the City of Evans, 1100 37th Street, Evans, Colorado 80620; phone number (970) 475-1113 and fax number (970) 330-3472.

### 1.2.2 ENGINEER

The ENGINEER is City of Evans, 1100 37th Street, Evans, Colorado 80620. The City Engineer is **Mazedur Hossain**, phone number **(970) 702-8534**. The City of Evans Project Manager is **Brian Stone** phone number **(970) 970-415-0207**. For this project, the CITY has contracted with **Sanbell**, to do the design of the improvements.

### 1.2.3 BID SUBMITTAL

Bids will be received by the City of Evans, Colorado (herein called the "CITY"), electronically via BidNet, as noted in the Advertisement for Bid.

**Each Bid must contain the following to be considered complete. Incomplete bids will be thrown out and not considered for award. Please order your submission as follows:**

- Company Overview and Description (please limit to one page)
- 1.5.1 – Non-Collusion Statement
- 1.5.2 – Bid Proposal
- 1.5.3 – Bid Schedule
- 1.5.4 – Bid Bond
- List of anticipated key personnel that will be working on the project including but not limited to the Project Manager, Superintendent and Foreman along with their qualifications and experience
- Minimum three (3) references from similar projects that include the client's name, contact information, and a brief project overview. Municipal/government funded projects preferred.

All bids must be made on the required bid sheet. All blank spaces for bid prices must be filled in, typewritten, and the bid sheet must be fully completed and executed when submitted. ***Please also include a copy of the bid sheet as a separate excel file.***

### 1.2.4 INFORMALITIES

The CITY may waive any informalities, minor defects, or reject any and all bids. Any bid may be withdrawn prior to the above scheduled time for the opening of bids or authorized postponement thereof. In the event of strikes, wars, acts of God or other good cause as determined by the City Manager, bid openings may be extended for a reasonable time not to exceed thirty calendar days. No bidder may withdraw a bid within 60 days after the actual date of the opening thereof. Should there be reasons why the contract cannot be awarded within the specified period; the time may be extended by mutual agreement between the CITY and the bidder.

### 1.2.5 CONDITIONS OF WORK

Bidders must satisfy themselves of the accuracy of the estimated quantities in the Bid Schedule(s) by examination of the site. After bids have been submitted, the bidder shall not assert that there was a misunderstanding concerning the quantities of work or of the nature of the work to be done.

The CITY shall provide to any and all bidders, prior to bidding, all information that is pertinent to

and delineates and describes the land owned and rights-of-way acquired upon request.

The Contract Documents contain the provisions required for the construction of the project. Information otherwise obtained from an officer, agent or employee of the CITY or any other person shall not affect the risks or obligations assumed by the CONTRACTOR or relieve them from fulfilling any of the conditions of the contract.

#### 1.2.6 BID SECURITY

Each bid must be accompanied by a Bid Bond payable to the City for five (5%) percent of the total amount of the bid. As soon as the bid prices have been compared, the CITY will return the bonds of all except the three lowest responsible bidders within three days after the date of the bid opening. When the Agreement is executed, the Bid Bonds of the two remaining unsuccessful bidders will be returned. The Bid Bond of the successful bidder will be retained until the Agreement, Payment Bond and Performance Bond have been executed and approved, after which it will be returned.

A Performance Bond and Payment Bond, each in the amount of One Hundred (100%) percent of the Contract Price, with a corporate surety approved by the CITY, will be required for the faithful performance of the contract.

#### 1.2.7 POWER OF ATTORNEY

Attorneys-in-fact who sign the Bid Bonds or Payment Bonds and Performance Bonds must file with each bond a certificate and effective dated copy of their Power of Attorney.

#### 1.2.8 PROJECT SCHEDULE

- |   |                   |
|---|-------------------|
| • Advertise Date                                    | December 18, 2025 |
| • Mandatory Prebid Meeting (2:00 p.m. MT)           | January 7, 2026   |
| • Questions Due                                     | January 9, 2026   |
| • Response to Questions                             | January 13, 2026  |
| • Solicitation Close and Bid Opening (2:00 p.m. MT) | January 20, 2026  |
| • Notice of Intent to Award (tentative)             | January 21, 2026  |
| • City Council Approval (tentative)                 | February 3, 2026  |
| • Notice to Proceed (tentative)                     | February 5, 2026  |

### 1.3 AWARD OF CONTRACT

The party to whom the contract is awarded will be required to execute the Agreement and obtain the Performance Bond, Payment Bond, and Certificates of Insurance within ten (10) calendar days from the date when Notice of Award is delivered to the bidder. The Notice of Award shall be accompanied by the necessary Agreement. In case of failure of the bidder to execute the Agreement and to furnish said Bonds and Certificates, the CITY may at its option, consider the bidder in default, in which case the Bid Bond accompanying the proposal shall become the property of the CITY. The CITY will be entitled to such other rights as may be granted by law.

The CITY within ten (10) days of receipt of acceptable Performance Bond, Payment Bond Certificates of Insurance and Agreement signed by the party to whom the Agreement was awarded, shall sign the Agreement and return to such party an executed duplicate of the Agreement. Should the CITY not execute the Agreement within such period, the bidder may, by

written notice, withdraw their signed Agreement. Such notice of withdrawal shall be effective upon receipt of the notice by the CITY.

The Notice to Proceed shall be issued within ten (10) days of the execution of the Agreement by the CITY or as otherwise stated in the Special Conditions. Should there be reasons why the Notice to Proceed cannot be issued within such period; the time may be extended by mutual agreement between the CITY and the CONTRACTOR. If the Notice to Proceed has not been issued within the ten (10) day period or within the period mutually agreed upon, the CONTRACTOR may terminate the Agreement without further liability on the part of either party.

The CITY may make such investigations as deemed necessary to determine the ability of the bidder to perform the work, and the bidder shall furnish to the CITY all such information and data for this purpose as the CITY may request. The CITY reserves the right to reject any bid if the evidence submitted by, or investigation of, such bidder fails to satisfy the CITY that such bidder is qualified to carry out the obligations of the Agreement and to complete the work contemplated therein. The CITY reserves the right to reject any conditional or qualified bid.

The CONTRACTOR shall commence work in accordance with the dates inserted in the Notice to Proceed issued by the CITY to the CONTRACTOR and shall complete the work as specified, within the time specified in the contract. In the event no written Notice to Proceed is issued by the CITY, the contract time as specified in the contract shall be counted from the first day of actual work on the project. All work shall be prosecuted in an orderly and diligent manner. The CONTRACTOR shall cooperate with, and conform to, the request of the CITY to expedite particular portions of the work or to suspend or transfer its operations on any portion of the work where such alteration of the CONTRACTOR's operations is deemed advisable by the CITY.

All applicable laws, ordinances, and the rules and regulations of all authorities having jurisdiction over construction of the project shall apply to the contract throughout.

Each bidder is responsible for inspecting the site and informing themselves of the conditions under which the work is to be performed and for reading and being thoroughly familiar with the contract documents. The bidder's inspection shall cover the ground structure, obstacles which may be encountered, location of water tables, and other matters relevant to the work both above and below ground. Where test boring logs, indicating underground conditions, are shown on the drawings, this data is for the bidder's information and to reflect the conditions observed at the time and place of drilling. Neither the CITY nor the ENGINEER shall be held responsible for any variance or deviation from the data shown on the drawings, as encountered during actual construction. The failure or omission of any bidder to do any of the foregoing shall in no way relieve any bidder from any obligation in respect to their bid. The successful bidder will not be allowed any extra compensation in the form of contract price or time by any matter or thing on which he could have fully informed the CITY of prior to the bidding.

The low bidder shall supply the names and addresses of major material suppliers and subcontractors when requested to do so by the CITY.

The OWNER reserves the right to reject any or all bids and to pass upon the regularity or waive any irregularities of the bidders and to determine the acceptability of the surety offered.

If Bid Schedules are set forth in the Proposals, the CONTRACTORS must bid on all the Schedules. The CONTRACTOR'S bid considered for award shall be for the combined low bid for the Base Bid and Force Account.

Portions of any project may have been termed "Alternates or Contingent" and the OWNER reserves the right to include or remove any or all of these Alternates from the Contract at their sole option or discretion.

#### 1.3.1 CONSIDERATION OF PROPOSALS

After the proposals are opened and read, they will be compared on the basis of the summation of the products of the approximate quantities shown in the bid schedule by the unit bid prices. The results of such comparisons will be immediately available to the public. In the event of a discrepancy between unit bid prices and extensions, the unit bid price shall govern.

The right is reserved to reject any or all proposals, to waive technicalities or to advertise for new proposals, if in the judgment of the awarding authority the best interests of the CITY will be promoted thereby.

#### 1.3.2 AWARD OF CONTRACT

The award of contract, if it is awarded, will be made within (60) calendar days after the opening of proposals to the lowest responsible and qualified bidder whose proposal complies with all the requirements prescribed. The successful bidder will be notified, by letter mailed to the address shown on their proposal, that their bid has been accepted and that they have been awarded the contract.

#### 1.3.3 CANCELLATION OF AWARD

The CITY reserves the right to cancel the award of any contract at any time before the execution of said contract by all parties without any liability against the CITY.

#### 1.3.4 EXECUTION AND APPROVAL OF CONTRACT

The Contract shall be signed by the successful bidder and returned, together with requisite attachments outlined in Section 1.5.7. All documents will be executed in triplicate and shall be submitted to the CITY within (10) calendar days after the date of award. If the signed Contract and Bond is returned by the successful bidder within (10) calendar days after award and if the Contract is not executed by the CITY within (60) days from date of award, the bidder shall have the right to withdraw its bid without penalty. No Contract shall be considered effective until it has been fully executed by all of the parties thereto.

#### 1.3.5 FAILURE TO EXECUTE CONTRACT

Failure to execute the Contract and file acceptable bonds within (10) calendar days after the date of award shall be just cause for the cancellation of the award and the forfeiture of the proposal guaranty which shall become the property of the CITY. The CITY may elect to waive forfeiture of the proposal guaranty only if it is determined that the bidder has made a good faith remedial error and that no damages were sustained by the CITY as a result of the failure by the successful bidder to execute the contract and file acceptable bonds within the time prescribed. Award may then be made to the next lowest responsible bidder, or the work may be re-advertised and constructed under contract or otherwise, as the CITY may decide.

## **1.4 THE CONTRACT: FOLLOWING EXECUTION**

### **1.4.1 MATERIALS**

Unless otherwise stipulated, the CONTRACTOR shall provide and pay for all materials, labor, water, tools, equipment, light power, transportation, and other facilities necessary for the execution and completion of the work. The CONTRACTOR shall furnish satisfactory evidence as to the kind and quality of materials.

### **1.4.2 PROGRESS SCHEDULE**

The CONTRACTOR shall submit, at such times as may reasonably be requested by the ENGINEER, schedules which shall show the order in which he proposes to carry on the work, with dates at which the CONTRACTOR will start the several parts of the work, and estimated dates of completion of the several parts. The Special Conditions or Drawings may require that certain phases or parts of the work be completed first or in a certain order. If the CONTRACTOR elects to use PERT or CPM charts, he shall furnish copies of them and all revisions thereto or amendments thereto as the work progresses to the ENGINEER upon request.

### **1.4.3 ASSIGNMENT OF CONTRACT**

No assignment by the CONTRACTOR of this contract or any part thereof or of the funds to be received thereunder by the CONTRACTOR will be recognized unless such assignment has had the written approval of the CITY and the surety has been given due notice of such assignment and has furnished written consent thereto. Such written approval by the CITY shall not relieve the CONTRACTOR of the obligations incurred by them under the terms of this contract. In addition to the usual recitals in assignment contracts, the following language must be set forth:

It is agreed that the funds to be paid to the assignee under this assignment are subject to a prior lien for services rendered or materials supplied for the performance of the work called for in said contract in favor of all persons, firms, or corporations rendering such services or supplying such materials."

### **1.4.4 SUBLETTING OF CONTRACT**

The CONTRACTOR shall as soon as practical after signing the contract, notify the ENGINEER in writing, giving the names and qualifications of all subcontractors proposed for work and shall not employ any that the ENGINEER may within a reasonable time object to. The CONTRACTOR will not be allowed to subcontract more than fifty percent (50%) of the total monetary value of the contract without prior approval of the OWNER. The CONTRACTOR shall notify the ENGINEER of each subcontract he awards, giving:

- A. Name, address, and telephone number of the subcontractor
- B. Branch of work covered
- C. Total price of subcontract
- D. Date of subcontract

Subcontractors, before commencing work, must file with the ENGINEER satisfactory certificates in duplicate showing insurance coverage. Failure of the subcontractor to provide such certificates shall not relieve the CONTRACTOR of its obligation to insure and to hold the CITY

harmless. Subcontractors shall also file with the ENGINEER copies of applicable permits and licenses required to do the subcontracted work.

#### 1.4.5 OTHER CONTRACTS

The CITY may award other contracts for additional work, and the CONTRACTOR shall fully cooperate with such other contractors and carefully fit its own work to that provided under the other contracts as may be directed by the ENGINEER. The CONTRACTOR shall not commit or permit any act that will interfere with the performance of work by any other contractor.

## 1.5 CONTRACT DOCUMENTS

### 1.5.1 NON-COLLUSION STATEMENT

\_\_\_\_\_, being first duly sworn, deposes and says that:

- (1) He is the \_\_\_\_\_ of  
(owner, partner, officer, representative or agent)  
\_\_\_\_\_, the  
(Company's Name)  
bidder that has submitted the attached bid;
- (2) He is fully informed respecting the preparation and contents of the attached bid and of all pertinent circumstances respecting such bid;
- (3) Such bid is genuine and is not a collusive or sham Bid;
- (4) Neither the said bidder nor any of its officers, partners, owners, agents, representatives, employees or parties in interest, including this affiant, has in any way colluded, conspired, connived or agreed, directly or indirectly with any other bidder, firm or person to submit a collusive or sham bid in connection with the contract for which the attached bid has been submitted or to refrain from bidding in connection with such contract, or has in any manner, directly or indirectly, sought by agreement or collusion or communication or conference with any other bidder, firm or person to fix the price or prices in the attached bid or of any other bidder, or to fix any overhead, profit or cost element of the bid price or the bid price of any unlawful agreement any advantage against the City of Evans or any person interested in the proposed contract; and
- (5) The price or prices quoted in the attached bid are fair and proper and are not tainted by a collusion, conspiracy, connivance, or unlawful agreement on the part of the bidder or any of its agents, representatives, owners, employees, or parties in interest, including this affiant.

Signed: \_\_\_\_\_

Title: \_\_\_\_\_

STATE OF COLORADO     )  
  ) ss.  
COUNTY OF \_\_\_\_\_ )

Subscribed and sworn to before me this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_\_.

\_\_\_\_\_  
Notary Public in and for Colorado

My Commission expires: \_\_\_\_\_

### 1.5.2 BID PROPOSAL

**Gateway Sign and Beautification Project at Evans Junction (31st Street and Hwy 85)**  
Proposal of \_\_\_\_\_ (hereinafter called bidder,  
doing business as \* \_\_\_\_\_ organized and existing  
under the laws of the State of \_\_\_\_\_, to the City of Evans (hereinafter  
called CITY).

In compliance with your Advertisement for Bids, bidder hereby proposes to perform all work for  
the **Gateway Sign and Beautification Project at Evans Junction (31st Street and Hwy 85)**  
in strict accordance with contract documents, within the time set forth therein, and at prices  
stated below.

By submission of this bid, each bidder certifies, and in cases of a joint bid, each party hereto  
certifies as to their own organization, that this bid has been arrived at independently, without  
consultation, communication, or agreement as to any matter relating to this bid with any other  
bidder or with any competitor.

Bidder hereby agrees to commence work under this contract on or before a date specified in the  
Special Conditions. Bidder further agrees to pay liquidated damages as provided in the Special  
Conditions.

Bidder acknowledges receipt of the following Addendum:

---

---

---

---

Bid shall include all applicable taxes and fees.

Bidder agrees to perform all work described in the contract documents in accordance with the  
attached Bid Schedule.

**\* Insert "a Corporation", "a Partnership", or "an Individual" as applicable.**

### 1.5.3 BID SCHEDULE

### **1.5.3 BID SCHEDULE**

**This page left intentionally blank.  
Please remove and insert bid schedule table page. Bid schedule included in additional  
documents on BidNet.**

1.5.4 BID BOND

KNOW ALL MEN BY THESE PRESENTS, that we, the undersigned, \_\_\_\_\_,  
as Principal, and \_\_\_\_\_, as surety, are hereby held and firmly bound unto the  
City of Evans in the penal sum of (\$\_\_\_\_\_) for the payment of which, well and  
truly to be made, we hereby jointly and severally bind ourselves, successors and assigns.

Signed this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_\_.

The condition of the above obligations is such that whereas the Principal has submitted to the  
City of Evans a certain bid, attached hereto and hereby made a part hereof, to enter into a  
contract in writing, for the

**Gateway Sign and Beautification Project at Evans Junction (31st Street and Hwy 85)**

NOW THEREFORE,

- (A) If said bid shall be rejected, or in the alternate,
- (B) If said bid shall be accepted and the Principal shall execute and deliver a contract in  
the form of contract attached hereto (properly) completed in accordance with said  
bid and shall furnish a bond for its faithful performance of said contract, and for the  
payment of all persons performing labor or furnishing materials in connection  
therewith, and shall in all other respects perform the agreement created by the  
acceptance of said bid,

then this obligation shall be void, otherwise, the same shall remain in force and effect; it being  
expressly understood and agreed that the liability of the Surety for any and all claims hereunder,  
in no event, exceed the penal amount of this obligation as herein stated.

The Surety, for value received, hereby stipulates and agrees that the obligations by any  
extension of the time within which the CITY may accept such bid; and said Surety does hereby  
waive notice of any such extension.

IN WITNESS WHEREOF, the Principal and the Surety have hereunder set their hands and  
seals, and such of them as are corporations have caused their corporate seals to be hereto  
affixed and these presents to be signed by their proper officers, the day and year first set forth  
above.

\_\_\_\_\_  
Principal

\_\_\_\_\_  
Surety

By:\_\_\_\_\_

1.5.5 NOTICE OF AWARD

TO:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

PROJECT DESCRIPTION:

**Gateway Sign and Beautification Project at Evans Junction (31st Street and Hwy 85)**

The CITY, represented by the undersigned, has considered the bid submitted by you for the above-described work in response to its Advertisement for Bids dated **March 14, 2025.**

You are hereby notified that your bid has been accepted for  
**Gateway Sign and Beautification Project at Evans Junction (31st Street and Hwy 85)**  
in the amount of \$.

You are required by the Information for Bidders to execute the Agreement and furnish the required Contractor's Performance Bond, Payment Bond, and Certificates of Insurance within ten (10) calendar days from the date of this Notice to you. If you fail to execute said Agreement and to furnish said bonds and certificates within ten (10) days from the date of this Notice, said CITY will be entitled to consider all your rights arising out of the CITY's acceptance of your bid as abandoned and as a forfeiture of your Bid Bond. The CITY will be entitled to such other rights as may be granted by law.

You are required to return an acknowledged copy of this Notice of Award to the CITY.

Dated this \_\_\_\_ day of \_\_\_\_\_, 20\_\_.

The City of Evans

By: \_\_\_\_\_  
Brian Stone, Economic Development Director

1.5.6 ACCEPTANCE OF NOTICE

Receipt of the above Notice of Award is hereby acknowledged on this, the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_.

By: \_\_\_\_\_

Title: \_\_\_\_\_

IMPORTANT: Surety companies executing bonds must appear on the Treasury Department's most current list (circular 570 as amended) and be authorized to transact business in the State of Colorado.

### 1.5.7 AGREEMENT

THIS AGREEMENT, made this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_, by and between the City of Evans, hereinafter called "CITY", and \_\_\_\_\_ doing business as \_\_\_\_\_ hereinafter called "CONTRACTOR".

WITNESSETH: That for and in consideration of the payments and agreements hereinafter mentioned:

The CONTRACTOR will commence and complete the phased construction of  
**Gateway Sign and Beautification Project at Evans Junction (31st Street and Hwy 85)**

- 1.
2. The CONTRACTOR shall furnish all material, supplies, tools, equipment, labor and other services necessary for the construction and completion of the project described herein.
3. The CONTRACTOR shall commence the work required by the Contract Documents in accordance with the date stated in the Special Conditions and shall complete the work within the time stated in the Special Conditions unless the period for completion is extended otherwise by the Contract Documents.
4. The CONTRACTOR agrees to perform all the work described in the Contract Documents and comply with the terms therein for the sum of \$\_\_\_\_\_ for the  
**Gateway Sign and Beautification Project at Evans Junction (31st Street and Hwy 85)**
5. The term "Contract Documents" means and includes the following:
  - (A) Advertisement for bids
  - (B) Information for Bidders
  - (C) Non-Collusion Statement
  - (D) Bid Proposal
  - (E) Bid Schedule
  - (F) Bid Bond
  - (G) Notice of Award
  - (H) Acceptance of Notice
  - (I) Agreement
  - (J) Payment Bond
  - (K) Performance Bond
  - (L) Certificate of Incorporation
  - (M) Certificates of Insurance
  - (N) Notice to Proceed
  - (O) Special Conditions
  - (P) General Conditions
  - (Q) Technical Provisions
  - (R) Change Order
  - (S) Addendum
    - No. \_\_\_\_\_, dated \_\_\_\_\_.
    - No. \_\_\_\_\_, dated \_\_\_\_\_.
    - No. \_\_\_\_\_, dated \_\_\_\_\_.
  - (T) Notice of Contractor's Settlement
  - (U) Final Receipt and Guarantee
  - (V) Other

6. The CITY will pay the CONTRACTOR in the manner and at such time as set forth in the General Conditions, such amounts required by the Contract Documents.
7. This Agreement shall be binding upon all parties hereto and their respective heirs, executors, administrators, successors, and assigns.

IN WITNESS WHEREOF, the parties hereto have executed, or caused to be executed by their duly authorized officials, this Agreement, each of which shall be deemed an original on the date first written above.

THE CITY OF EVANS

CONTRACTOR

BY: \_\_\_\_\_  
Mark C. Clark, Mayor

BY: \_\_\_\_\_  
NAME: \_\_\_\_\_  
TITLE: \_\_\_\_\_  
ADDRESS: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

(SEAL)

ATTEST:

NAME: \_\_\_\_\_  
TITLE: \_\_\_\_\_

APPROVED AS TO FORM:

\_\_\_\_\_  
Drew Lyman, Evans City Attorney

APPROVED AS TO SUBSTANCE

\_\_\_\_\_  
Cody R. Sims, Evans City Manager

### 1.5.8 PERFORMANCE BOND

KNOW ALL MEN BY THESE PRESENTS: that

\_\_\_\_\_  
Name of Contractor

\_\_\_\_\_  
Address of Contractor

a \_\_\_\_\_, hereinafter called Principal, Corporation, Partnership or Individual

\_\_\_\_\_  
Name of Surety

\_\_\_\_\_  
Address of Surety

hereinafter called Surety, are held and firmly bound unto the City of Evans, 1100 37th Street, Evans, Colorado 80620, hereinafter called CITY, in the penal sum of \$ \_\_\_\_\_ in lawful money

of the United States, for the payment of which sum well and truly to be made, we bind ourselves, successors, and assigns, jointly, severally, firmly by these presents.

THE CONDITION OF THIS OBLIGATION is such that whereas the Principal entered into a certain Contract with the CITY, dated the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_\_, a copy of which is hereto attached and made a part hereof for the construction of:

#### **Gateway Sign and Beautification Project at Evans Junction (31st Street and Hwy 85)**

NOW, THEREFORE, if the Principal shall well, truly, and faithfully perform its duties, all the undertakings, covenants, terms, conditions, and agreements of said contract during the original term thereof, and any extensions thereof which may be granted by the CITY, with or without notice to the Surety and during the two-year guarantee period, and if he shall satisfy all claims and demands incurred under such contract, and shall fully indemnify and save harmless the CITY from all costs and damages which it may suffer by reason of failure to do so, and shall reimburse and repay the CITY all outlay and expense which the CITY may incur in making good any default, then this obligation shall be void; otherwise to remain in full force and effect.

PROVIDED, FURTHER, that the said Surety, for value received hereby stipulates and agrees that no change, extension of time, alteration or addition to the terms of the contract or to work to be performed thereunder or the specifications accompanying the same shall in any ways affect its obligation on this bond, and it does hereby waive notice of any such change, extension of time, alteration or addition to the terms of the contract or to the work or to the specifications.

PROVIDED, FURTHER, that no final settlement between the CITY and the CONTRACTOR shall abridge the right of any beneficiary hereunder, whose claim may be unsatisfied.

IN WITNESS WHEREOF, this instrument is executed this \_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

ATTEST:

\_\_\_\_\_  
Principal

\_\_\_\_\_  
Principal Secretary

By: \_\_\_\_\_ (S)

(SEAL)

\_\_\_\_\_  
Witness as to Principal

\_\_\_\_\_  
Address

ATTEST:

\_\_\_\_\_  
Surety Secretary

(SEAL)

\_\_\_\_\_  
Witness as to Surety

By: \_\_\_\_\_  
Attorney-in-Fact

\_\_\_\_\_  
Address

\_\_\_\_\_  
Address

NOTE: Date of bond must not be prior to date of contract. If CONTRACTOR is a partnership, all partners should execute bond.

IMPORTANT: Surety companies executing bonds must appear on the Treasury Department's most current list (circular 570, as amended) and be authorized to transact business in the state where the project is located.

1.5.9 PAYMENT BOND

KNOW ALL MEN BY THESE PRESENTS: that

\_\_\_\_\_  
Name of Contractor

\_\_\_\_\_  
Address of Contractor

A \_\_\_\_\_, hereinafter called Principal, and  
Corporation, Partnership or Individual

\_\_\_\_\_  
Name of Surety

\_\_\_\_\_  
Address of Surety

hereinafter called Surety, are held and firmly bound unto the City of Evans, 1100 37th Street, Evans, Colorado 80620 hereinafter called "CITY", in the penal sum of \$ \_\_\_\_\_ in lawful money of the United States, for the payment of which sum well and truly to be made, we bind ourselves, successors, and assigns, jointly and severally, firmly by these presents.

THE CONDITION OF THIS OBLIGATION is such that whereas, the Principal entered into a certain contract with the CITY, dated the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_, a copy of which is hereto attached and made a part hereof for the construction of:

**Gateway Sign and Beautification Project at Evans Junction (31st Street and Hwy 85)**

NOW, THEREFORE, if the Principal shall, during the entire length of said contract and any extension thereof, promptly make payment to all persons, firms, subcontractors, and corporations furnishing materials for or performing labor in the prosecution of the work provided for in such contract, and any authorized extension or modification thereof, including all amounts due for materials, lubricants, oil, gasoline, coal and coke, repairs on machinery, equipment and tools, consumed or used in connection with the construction of such work, and all insurance premiums on said work, and for all labor performed in such work whether by subcontractor or otherwise, then this obligation shall be void; otherwise to remain in full force and effect.

PROVIDED, FURTHER, that the said Surety, for value received hereby stipulates and agrees that no change, extension of time, alteration, or addition to the terms of the contract or to the work or to be performed thereunder or the specifications accompanying the same shall in any way affect its obligation on time, alteration or addition to the terms of the contract or to the work or to the specifications.

PROVIDED, FURTHER, that no final settlement between the CITY and the CONTRACTOR shall abridge the right of any beneficiary hereunder, whose claim may be unsatisfied.

IN WITNESS WHEREOF, this instrument is executed in \_\_\_\_\_ (number) counterparts, each one of which shall be deemed an original, this the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

ATTEST:

\_\_\_\_\_  
Principal

\_\_\_\_\_  
Principal Secretary

By: \_\_\_\_\_

(SEAL)

\_\_\_\_\_  
Witness as to Principal

\_\_\_\_\_  
Address

ATTEST:

\_\_\_\_\_  
Surety Secretary

(SEAL)

\_\_\_\_\_  
Witness as to Surety

By: \_\_\_\_\_  
Attorney-in-Fact

\_\_\_\_\_  
Address

\_\_\_\_\_  
Address

NOTE: Date of bond must not be prior to date of contract. If CONTRACTOR is a partnership, all partners should execute bond.

IMPORTANT: Surety companies executing bonds for must appear on the Treasury Department's most current list (circular 570, as amended) and be authorized to transact business in the state where the project is located.

1.5.10 NOTICE TO PROCEED

TO: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

DATE: \_\_\_\_\_

Project:

**Gateway Sign and Beautification Project at Evans Junction (31st Street and Hwy 85)**

You are hereby notified to commence work in accordance with the Agreement dated **{Agreement Date}**, on or before **{Start Date}**, and you are to complete the work within **{Number of Work Days}** consecutive working days thereafter. The date of completion of all work is therefore **{Finish Date}**.

THE CITY OF EVANS

By: \_\_\_\_\_  
City Engineer

1.5.11 ACCEPTANCE OF NOTICE

Receipt of the above Notice to Proceed is hereby acknowledged by:

\_\_\_\_\_  
\_\_\_\_\_

this the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

By: \_\_\_\_\_

Title: \_\_\_\_\_



---

# Change Order Request Form

---

**Date:** \_\_\_\_\_ **Change Order No.** \_\_\_\_\_

**Project:** \_\_\_\_\_

**Contractor:** \_\_\_\_\_

**Contractor Representative:** \_\_\_\_\_

**Original Contract Amount:** \$ \_\_\_\_\_

**Original Project Contingency:** \$ \_\_\_\_\_

**Current Contract Amount (incl. Change Orders):** \$ \_\_\_\_\_

**Project Contingency Remaining (incl. Change Orders):** \$ \_\_\_\_\_

- ☐ This Change Order will have no financial impact.
- ☐ This Change Order will decrease the total project cost.
- ☐ This Change Order will increase the total project cost.
- ☐ This Change Order will require the use of project contingency.
- ☐ This Change Order will require City Council reappropriation.

**Amount of this Change Order Request:** \$ \_\_\_\_\_

**Number of Additional Working Days Requested:** \_\_\_\_\_

**Justification for Change Order Request (please include any supporting documentation as an attachment to this form):**

---

# Change Order Request Form

---

## ***Acknowledgement***

This Change Order Request Form has been established in accordance with the adopted Procurement Policy for the City of Evans. Work related to this Change Order Request shall not be completed until all required approvals have been granted and the contractor has received a written Notice to Proceed from the City.

***City Engineer or Initiating Party:***

---

***Contractor Representative:***

---

***Department Director (If  
Applicable):***

---

***City Manager (If Applicable):***

---

***City Council (If Applicable):***

---

#### 1.5.13 NOTICE OF CONTRACTOR'S SETTLEMENT

This is to notify all persons interested that the City of Evans, Colorado will make final payment to **{Contractor's Name}** for work completed on **Gateway Sign and Beautification Project at Evans Junction (31st Street and Hwy 85)**

Said final payment will be made on **{Final Payment Date}**.

Anyone having claims in conjunction with this project may file same with the undersigned no later than **{Wednesday Before Final Payment Date}**.

CITY OF EVANS

By: \_\_\_\_\_  
Brian Stone, Economic Development Director

Dated: \_\_\_\_\_  
The Greeley Tribune

#### 1.5.14 FINAL RECEIPT AND GUARANTEE

CITY OF EVANS

Date: \_\_\_\_\_

Received this date of **{Final Payment Date}**, as full and final payment of the cost of improvements provided for in the Contract executed by **{Contractor's Name}** and Payee on or about **{Agreement Date}**, together with all amendments, change orders, and additions thereto, the sum of Dollars (\$**{Final Payment Amount}**), by check, being the remainder of the full amount accrued to the undersigned under the above-mentioned contract, including any and all extra work performed, and any and all materials and incidentals furnished by the undersigned thereunder. For this amount and the additional consideration of One Dollar (\$1.00), the undersigned hereby releases the City of Evans from any claims whatsoever resulting from said contract and all work performed thereunder.

The undersigned, by these presents, certifies that all persons doing work upon or furnishing materials for said improvements under the foregoing contract and all additions thereto have been paid in full. The undersigned further certifies that all work has been completed in a workmanlike manner in conformity with the project's plans and specifications. That should any portion of said work or material(s) prove defective within **two (2) years** from the date of initial acceptance of the entire project by the City of Evans, the undersigned shall replace any such defective material(s) and remedy any such defective work to the satisfaction of the City of Evans, and shall defend and indemnify expenses and charges of every kind which may arise as a result of any such defective material(s) and workmanship during said period.

**The Performance and Maintenance Bond for this contract shall remain in effect for the two (2) year period of the guarantee.**

**Gateway Sign and Beautification Project at Evans Junction (31st Street and Hwy 85)**

Signature: \_\_\_\_\_

Name: \_\_\_\_\_

Title: \_\_\_\_\_

## 1.6 INSURANCE REQUIREMENTS

The CONTRACTOR shall secure and maintain such insurance policies as will protect themselves, their subcontractors, and the City of Evans, from claims for bodily injuries, death or property damage, which may arise from operations under this contract whether such operations be by themselves or by any subcontractor or anyone employed by them directly or indirectly. The following insurance policies are required:

- (a) Statutory Worker's Compensation
- (b) Commercial General Liability
  - General Aggregate \$ 2,000,000
  - Products/ \$ 2,000,000
  - (Completed Operations Aggregate)
  - Each Occurrence \$ 1,000,000
  - Personal & Advertising Injury \$ 1,000,000
  - Fire Damage \$ 50,000
  - Medical Expense \$ 5,000
- (c) Automobile Liability
  - Bodily Injury and Property Damage \$ 1,000,000
  - (Combined Single Limit)
- (d) Builders Risk/Installation Floater Full Replacement Cost
  - Be written on a Builder's Risk "All-Risk" or on Peril
  - or Special Causes of Loss policy form that shall at
  - least include insurance for physical loss and damage
  - to the Work, temporary buildings, false work, and
  - Work in transit and shall insure against at least the
  - following perils: fire, lightning, extended coverage,
  - theft, vandalism and malicious mischief, collapse,
  - debris removal, demolition occasioned by enforcement of laws and regulations,
  - water damage.

Certificates of Insurance must show "City of Evans, its employees and agents" as an Additional Insured.

All policies shall be for not less than the amounts set forth above or as stated in the Special Conditions. Other forms of insurance shall also be provided if called for by the Special Conditions.

Certificates or copies of policy of such insurance shall be filed with the CITY and shall be subject to its approval as to adequacy of protection, within the requirements of the specifications. Said Certificates of Insurance shall contain a 30-day written notice of cancellation in favor of the CITY.

## ARTICLE 2.0

### GENERAL CONDITIONS

#### INDEX

##### CONTENTS

2.1	DEFINITIONS .....	3
2.1.1	ABBREVIATIONS.....	3
2.1.2	GENERAL DEFINITIONS AND TERMS .....	10
2.2	GENERAL CONTRACT REQUIREMENTS .....	20
2.2.1	FAMILIARITY WITH WORK.....	20
2.2.2	CHANGED CONDITIONS.....	20
2.2.3	ORDER OF COMPLETION.....	20
2.2.4	DESIGN AND INSTRUCTIONS .....	21
2.2.5	SURVEYS.....	21
2.2.6	CLAIMS.....	21
2.2.7	EXECUTION AND CORRELATION OF DOCUMENTS.....	21
2.2.8	MATERIALS AND APPLIANCES.....	21
2.2.9	EMPLOYEES.....	21
2.2.10	ROYALTIES AND PATENTS.....	22
2.2.11	PERMITS, LICENSES AND REGULATIONS.....	22
2.2.12	INSPECTION OF WORK .....	22
2.2.13	SUPERINTENDENTS .....	23
2.2.14	PRECONTRACT EXAMINATION AND DISCOVERY OF DISCREPANCIES DURING WORK.....	23
2.2.15	CHANGES IN THE WORK.....	23
2.2.16	EXTENSION OF TIME .....	24
2.2.17	SUSPENSION OF WORK.....	24
2.2.18	THE CITY'S RIGHT TO TERMINATE CONTRACT .....	25
2.2.19	CONTRACTOR'S RIGHT TO STOP WORK OR TERMINATE CONTRACT .....	25
2.2.20	CANCELLATION OF CONTRACT.....	25
2.2.21	CORRECTION OF WORK BEFORE FINAL PAYMENT .....	25
2.2.22	REMOVAL OF EQUIPMENT .....	26
2.2.23	RESPONSIBILITY FOR WORK.....	26
2.2.24	PARTIAL COMPLETION AND ACCEPTANCE.....	26
2.2.25	PAYMENT WITHHELD PRIOR TO FINAL ACCEPTANCE OF WORK.....	26
2.2.26	CONTRACTOR'S INSURANCE AND INDEMNIFICATION .....	27
2.2.27	SURETY BONDS .....	28
2.2.28	CONTRACTOR'S INSURANCE.....	28
2.2.29	ASSIGNMENT .....	28
2.2.30	RIGHTS OF VARIOUS INTERESTS .....	29
2.2.31	ENGINEER'S STATUS .....	29
2.2.32	ENGINEER'S DECISIONS.....	29
2.2.33	ARBITRATION.....	30
2.2.34	ACCEPTANCE AND FINAL PAYMENT .....	30
2.2.35	LIQUIDATED DAMAGES .....	30
2.2.36	ADVANCE NOTICE.....	31
2.2.37	WORK DONE WITHOUT LINES OR GRADES .....	31
2.2.38	TAXES .....	31
2.3	LEGAL RELATIONS & RESPONSIBILITIES TO PUBLIC .....	31

2.3.1	LEGAL RELATIONS AND RESPONSIBILITY TO PUBLIC .....	31
2.3.2	PROJECT SAFETY .....	32
2.3.3	PROTECTION OF THE PUBLIC AND OF WORK AND PROPERTY .....	32
2.3.4	EQUAL OPPORTUNITY .....	32
2.4	MATERIALS & WORKMANSHIP .....	33
2.4.1	GUARANTEES .....	33
2.4.2	WARRANTIES .....	34
2.5	MEASUREMENT & PAYMENT .....	34
2.5.1	PAYMENT .....	34
2.5.2	PAY QUANTITIES .....	34
2.6	SCOPE OF WORK .....	34
2.6.1	CHANGES IN THE WORK .....	34
2.6.2	SUBLETTING OF CONTRACT .....	35
2.6.3	SEPARATE CONTRACTS .....	35
2.6.4	SUBCONTRACTS .....	35
2.6.5	UNDERGROUND OBSTRUCTIONS .....	35
2.6.6	EMERGENCY WORK .....	36
2.6.7	CLEANING UP .....	36

## 2.1 DEFINITIONS

- (a) The Contract Documents shall consist of the Advertisement for Bids, Information for Bidders, Non-Collusion Statement, Bid Proposal, Bid Bond, Notice of Award, Agreement, Performance Bond, Payment Bond, Insurance Requirements, Notice to Proceed, Change Order, Notice of Contractor's Settlement, Final Receipt and Guarantee, Drawings, Specifications, and Special and General Conditions, including all modifications thereof incorporated in any of the documents before and after the execution of the Contract.
- (b) The CITY and the CONTRACTOR are those named as such in the Agreement. They are treated through the Contract Document as if each were of singular number and masculine gender.
- (c) Wherever in this Contract the word "ENGINEER" is used, it shall be understood as referring to the City Engineer, acting personally or through any assistants or assigns.
- (d) Any written notice served pursuant to the terms of the Agreement shall be deemed to have been duly served as if delivered in person or by registered mail to the individual, or to a partner, or to an officer of the corporation for whom it is intended, or any authorized representative thereof.
- (e) The term "subcontractor" shall mean anyone, other than the contractor, who furnished at the site, under an agreement with the CONTRACTOR, labor, or labor and materials, or labor and equipment, but shall not include any person who furnished services of a personal nature.
- (f) Work shall mean the furnishing of all labor, materials, equipment, and other incidentals necessary to the successful completion of the Contract and the carrying out of all duties and obligations imposed by the Contract.
- (g) Extra work shall mean such additional labor, materials, equipment, and other incidentals as are required to complete the Contract for the purpose for which it was intended but was shown on the Drawings or called for in the Specifications or is authorized by the CITY in addition to that work called for in the Drawings and Specifications.
- (h) Dispute shall mean lack of agreement between any parties that have any obligations, duties, or responsibilities under the terms of the Contract Drawings or Specifications.
- (i) Mobilization shall consist of preparatory work and operations, including, but not limited to, those necessary for the movement of personnel, equipment, supplies and incidentals to the project site; for the establishment of all offices, buildings and other facilities necessary for work on the project; and for all other work and operations which must be performed in order to begin work on the various items on the project site.

### 2.1.1 ABBREVIATIONS

Wherever the following abbreviations are used in these general conditions, supplemental condition, specifications, standard details or on the drawings, they are to be construed the same as the respective expressions represented.

AASHTO

American Association of State Highway and Transportation  
Officials

AAN	American Association of Nurserymen
AB	Aggregate Base
Aban	Abandon
ABC	Aggregate base course
AC	Asphalt cement or concrete
ACB	Asphalt concrete base
ACI	American Concrete Institute
ACP	Asbestos cement pipe
ACPA	American Concrete Pipe Association
ACWS	Asphalt concrete wearing surface
AGC	Associated General Contractors of America, Inc.
Agg	Aggregate
Ahd	Ahead
AIA	American Institute of Architects
AIEE	American Institute of Electrical Engineers
AISC	American Institute of Steel Construction
ANSI	American National Standards Institute
APA	American Plywood Association
Approx	Approximate
APWA	American Public Works Association
AR	Aged residue
ASCE	American Society of Civil Engineers
ASME	American Society of Mechanical Engineers
Asph	Asphalt
ASTM	American Society for Testing Materials
Ave	Avenue
AWPA	American Wood Preservers Association
AWSC	American Welding Society Code
AWWA	American Water Works Association
Bbl	Barrel
BC	Beginning of curve
BCR	Beginning of curb return
Beg	Beginning
Bk	Book or Back
Blvd	Boulevard
BM	Bench Mark or Board Measure
Brg	Bearing
BST	Bituminous Surface Treatment
BTB	Bituminous Treated Base
BTU	British Thermal Units
BVC	Beginning of vertical curve
BVCE	Beginning of vertical curve elevation
BVCS	Beginning of vertical curve station
C	Centigrade or Curb
CB	Catch Basin
CBF&C	Catch basin frame & cover
CC or C/C	Center to Center
CCA	Colorado Contractor's Association, Inc.
CDOT	Colorado Department of Transportation

CE	City or County Engineer
Cem	Cement
CF	Curb face
cfs	Cubic Feet per second
CIP	Cast Iron pipe
CIPP	Cast-in-place concrete pipe
CL or C	Centerline
Cm	Centimeter
CMP	Corrugated metal pipe
CO	Clean out
Col	Column
Conc	Concrete
Const	Construct
CP	Concrete pipe(non-reinforced)
CRS	Colorado Revised Statutes
CTB	Cement Treated Base
Cu	Cubic
CY	Cubic Yards
Deg	Degree
DF	Douglas Fir
DG	Decomposed granite
Dia	Diameter
Dim	Dimension
DIP	Ductile Iron Pipe
Div	Division
Dr	Drive
DRCOG	Denver Regional Council of Governments
Drwg	Drawing
Dwy	Driveway
Ea	Each
Ease	Easement
E	East
EC	End of curve
ECR	End of curb return
El or Elv	Elevation
Equa or Eq	Equation
EVC	End of vertical curve
EVCE	End of vertical curve elevation
EVCS	End of vertical curve station
Ex or Exist	Existing
F	Fahrenheit
FB	Field Book
F & C	Frame & cover
FH	Fire hydrant
FL or F	Floor line or flow line
FIEI	Floor Elevation
Fnd	Found
fps	Feet per second

FS	Finished surface
FSS	Federal Specifications and Standards
Ft	Foot or feet
G	Gutter
Ga	Gage
Galv	Galvanized
GL	Ground line
gpm	Gallons per minute
Gr	Grade
H	High or height
HC	House connection
Hdwl	Headwall
Horiz	Horizontal
Hwy	Highway
ID	Improvement District or inside diameter
IE	Invert Elevation
IEEE	Institute of Electrical and Electronic Engineers
In	Inch
Inv	Invert
IP	Iron Pipe
IPS	Iron Pipe Size
Irrig	Irrigation
Jt	Joint
JC	Junction Chamber
Jct	Junction
JS	Junction Structure
L	Length
Lb	Pound
L&T	Lead and tack
LD	Local depression
LF	Linear Feet
LH	Lamp hole
Lin	Linear
Long	Longitudinal
Lt	Left
M	Map or maps
Max	Maximum
Meas	Measured
MH	Manhole
MHF&C	Manhole frame and cover
Min	Minutes or minimum
Misc	Miscellaneous
MLorM	Monument line
Mm	Millimeter
Mon	Monolithic or monument

MTD	Multiple tile duct
MUTCD	Manual of Uniform Traffic Control Devices
N	North
NBS	National Bureau of Standards
NCPI	National Clay Pipe Institute
NE	Northeast
NEC	National Electric Code
NEMA	National Electrical Manufacturer's Association
NFPA	National Fire Protection Association
NP	Non-plastic
NPI	Non pay item
NSC	National Safety Council
NSF	National Sanitation Foundation
NW	Northwest
No	Number
OC	On center
OD	Outside diameter
Oz	Ounces
PC	Point of curvature
PCR	Point of curb return
PCC	Point of compound curve or Portland Cement Concrete
PI	Point of intersection or plastic index
PL	Property line
POC	Point of Curve
POS	Point of Spiral
PP	Power pole
ppm	Parts per million
PRC	Point of reverse curve
Prod	Proposed or property
psi	Pounds per square inch
psf	Pounds per square foot
PTorPOT	Point of Tangent
P&TP	Power and telephone pole
Pvmt	Pavement
Q	Rate of flow
R	Radius
RC	Reinforced concrete
RCP	Reinforced concrete pipe
Rd	Road
Rdwy	Roadway
Reinf	Reinforced, Reinforcing
Ret Wall	Retaining Wall
RGRCP	Rubber Gasket Reinforced Concrete Pipe
rpm	Revolutions Per Minute
Rt	Right
R/W or Row	Right-of-way

S	South or slope
SAE	Society of Automotive Engineers
San	Sanitary
SC	Spiral to Curve
SCCP	Steel cylinder concrete pipe
SD	Storm drain or Sewer District
SDDTC	Storm Drainage Design and Technical Criteria
Sdl	Saddle
Sec	Seconds
Sect	Section
SE	Southeast
SF	Square feet
Sht	Sheet
Spec	Specifications
SPR	Simplified Practice Recommendation
SpMH	Special manhole
Sq Ft Yd	Square Foot, Yard
SS	Sanitary sewer
St	Street
Sta	Station
Std	Standard
Str gr	Structural grade
Struct	Structure or structural
SW	Southwest
SY	Square Yard
T	Tangent Distance
Tel	Telephone
Temp	Temporary
TH	Test hole
TP	Telephone pole
Tr	Tract
Trans	Transition
TS	Traffic signal or Tangent to spiral
TSC	Traffic signal conduit
Typ	Typical
UD & FCD	Urban Drainage and Floor Control District
USDCM	Urban Storm Drainage Criteria Manual
UL	Underwriters Laboratories
USC&GS	United States Coast and Geodetic Survey
USGS	United States Geological Survey
V	Velocity of flow
VC	Vertical curve
VCP	Vitrified clay pipe
Vert	Vertical
W	West or width
WI	Wrought iron

WS	Wearing surface
Wt	Weight
Yd	Yard
'	feet or minutes
"	inches or seconds
o	degrees
%	percent
#	number or pound
@	at
/	per
=	equals

## 2.1.2 GENERAL DEFINITIONS AND TERMS

Whenever in these specifications or in other contract documents the following terms or pronouns in place of them are used, the intent and meaning shall be interpreted as follows:

**Addendum:** A Supplement to any of the Contract Documents issued, in writing, after advertisement of but prior to the opening of bids for a contract.

**Advertisement:** The public announcement, as required by law, inviting bids for work to be performed or materials to be furnished.

**Agency:** The government agency for which the construction is being done, either by permit or contract.

**Agreement:** The written agreement between OWNER and CONTRACTOR covering the Work to be performed; other Contract Documents are made a part thereof as provided therein.

**Application for Payment:** The form accepted by the ENGINEER which is to be used by CONTRACTOR in requesting progress or final payment and which is to include such supporting documentation as required by the Contract Documents.

**Award:** The formal action of the governing body in accepting a proposal.

**Backfill:** Material placed in an excavated space to fill such space. For trenches this space will be the area from 1 foot above the top of the pipe or conduit to the existing or proposed finished grade of pavement.

**Base Course:** The upper course of the granular base of a pavement or the lower course of an asphalt concrete pavement structure.

**Bedding:** Is the material placed in the area from the bottom of the trench to 1 foot above the top of the pipe or conduit.

**Bid:** The offer or proposal of the Bidder submitted on the prescribed form setting forth the prices for the Work to be performed.

**Bidder:** Any qualified individual, firm, partnership, corporation or combination thereof, acting directly or through a duly authorized representative who legally submits a proposal for the advertised work.

**Bond Issue Project:** A project financed from bonds issued by the CITY pledging credit or a revenue resource.

**Bridge:** A structure, including supports, erected over a depression or an obstruction, as water, highway, or railway, and having a track or passageway for carrying traffic or other moving loads and having a length measured along the center of roadway of more than 20 feet between undercopings of abutments or extreme ends of openings for multiple boxes.

(Length) The length of a bridge structure is the over-all length measured along the line of survey stationing back to back of backwalls of abutments, if present, otherwise end to end of the bridge floor; but in no case less than the total clear opening of the structure.

(Roadway Width) The clear width measured at right angles to the longitudinal centerline of the bridge between the bottom of curbs or guard timbers or in the case of multiple height of curbs, between the bottom of the lower risers.

**Budget Project:** A project financed by funds from General Tax levies and shared revenue funds set aside in the annual budget adopted by the Evans City Council.

**Building:** Any structure built for the support, shelter, or enclosure of persons, animals, chattel or movable property.

**Building Code:** A regulation adopted by the governing body establishing minimum standards of construction for the protection of the public health, safety, and welfare in terms of measured performance rather than in terms of rigid specifications of materials and methods.

**Calendar Day:** Every day shown on the calendar.

**Change Order:** A written order issued by the ENGINEER to the CONTRACTOR to make changes in the work or to perform extra work and setting forth conditions for payment and/or adjustment in time of completion.

**City:** A municipal corporation, organized and existing under and by virtue of the laws of the State of Colorado.

**City Clerk:** The duly authorized person who performs the duties of clerk for the Contracting Agency.

**Completion Time:** The number of calendar days for completion of an act, including authorized time extensions. In case a calendar date of completion is shown in the proposal in lieu of the number of calendar days, the contract shall be completed by that date. The time within which an act is to be done shall be computed by excluding the first and including the last day; and if the last day be Sunday or a legal holiday, that shall be excluded.

**Conflicting Utility Line:** An existing utility line, shown or not shown on the drawings, is a conflicting line when any part falls within the trench pay widths as listed or within the dimensions, as shown on the drawings, for appurtenant structures.

**Construction Project:** The erection, installation, remodeling, alteration, of durable facilities upon, under, or over the ground. This shall include, but is not limited to buildings, roadways and utility pipes, lines, poles or other structures.

**Contingent Bid Item:** This is a minor bid item which is likely, but not certain, to occur during the course of work. If the ENGINEER determines that this work is required, the CONTRACTOR will accomplish the work and payment will be made based on the contingent unit bid price included in the proposal. Since the quantity listed in the

proposal is primarily for bid comparison, the amount of work required by the ENGINEER may vary materially from this.

**Contract:** The written instrument executed by the CONTRACTOR and the Contracting Agency by which the CONTRACTOR is bound to furnish all labor, equipment, and materials and to perform the work specified, and by which the Contracting Agency is obligated to compensate the CONTRACTOR therefore at the prices set forth therein. The Contract Documents are herewith by reference made a part of the contract as if fully set forth therein.

**Contract Documents:** The Agreement, Addenda (which pertain to the Contract Documents), CONTRACTOR's Bid (including documentation accompanying the Bid and any post Bid documentation submitted prior to the Notice of Award) when attached as an exhibit to the Agreement, the Bonds, these General Conditions, the Supplementary Conditions, the Specifications and the Drawings as the same are more specifically identified in the Agreement, together with all amendments, modifications and supplements issued on or after the Effective Date of the Agreement.

**Contracting Agency:** The legal entity that has contracted for the performance of the work or for whom the work is being performed.

**Contractor:** The individual, firm, partnership, corporation or combination thereof entering into a contract with the Contracting Agency to perform the advertised work.

**Council:** The City Council that by law constitutes the Legislative Department of the City organized and existing under and by virtue of the laws of the State of Colorado.

**Culvert:** Any structure not classified as a bridge, which provides an opening under or adjacent to the roadway.

**Days:** Unless otherwise designated, days will be understood to mean calendar days.

**Emergency:** Unforeseen occurrences and combinations of circumstances involving the public welfare or the protection of work already done under the Contract Documents, or which endanger life or property and call for immediate action or remedy.

**Engineer:** The person, appointed as ENGINEER by the CITY acting directly or through their duly authorized representative.

**Equipment:** (Construction)-All machinery and equipment, together with the necessary supplies for upkeep and maintenance, and tools and apparatus necessary for the proper construction and acceptable completion of work.

(Installed)-All material or articles used in equipping a facility as furnishings or apparatus to fulfill a functional design.

**Extra Work:** An item of work not provided for in the contract as awarded but found essential to the satisfactory completion of the contract within its intended scope.

**Field Order:** A written set of emergency instructions to the CONTRACTOR issued only where the time required for preparation and execution of a formal Change Order would

result in a delay or a stoppage of work, or would allow a hazardous condition to exist.

**Fixed Bid Quantity:** A payment item to be paid at a unit price, but with a defined quantity amount in the contract. Deviation within +/- 25% to be paid per the contract amount and deviation beyond +/-25% may be re-negotiated by mutual agreement between the City and Contractor in accordance with CDOT Standard Specification (2017) Section 104.02.c.

**Flooding:** Flooding will consist of the inundation of the entire lift with water, puddled with poles or bars to insure saturation of the entire lift.

**Foundation:** For buildings or structures, this will be the substructure. For pipe this will be the native material or prepared material on which the pipe rests; normally, this is the bottom grade line of the trench.

**Full Depth Pavement:** An asphalt concrete pavement structure in which the granular base and sub-base are replaced by equivalent structural thickness of asphalt concrete.

**General Conditions:** Uniform general specifications adopted as standard specifications by the ENGINEER.

**Holiday:** Holidays recognized by collective bargaining agreements in the State of Colorado are:

- New Year's Day
- Memorial Day
- Independence Day
- Labor Day
- Thanksgiving Day
- Christmas Day

Additional holidays recognizable by the State of Colorado Cities and Counties are:

- Martin Luther King's Birthday
- Presidents Day
- Columbus Day
- Veteran's Day
- General Election Day in even-numbered years

When New Year's Day, Independence Day or Christmas Day fall on Sunday, the following Monday shall be considered a holiday.

Additional legal holidays, when designated by the State Governor or President of the United States, will also be recognized by the State, City and/or County.

**Improvement District Project:** A project financed by assessments against the property included in a special assessment district authorized under, or implemented by, an act of the legislature of the State and/or a procedural ordinance of the City or County.

**Inspector:** The ENGINEER's authorized representative assigned to make detailed inspections of contract performance.

**Jetting:** Jetting is the densification of material, using a continuous supply of water,

under pressure, transmitted to the material through a rigid pipe of sufficient length to reach the bottom of the lift being densified. In all cases, the entire lift will be completely saturated working from the top to the bottom.

**Laboratory:** The established materials testing laboratory of the Contracting Agency's Engineering Department, or other laboratories acceptable to and/or authorized by the ENGINEER to test materials and work involved in the Contract.

**Liquidated Damages:** A daily charge made against the CONTRACTOR for each working day, including free time, that any work shall remain uncompleted after elapse of Contract time.

**Major Item:** Any item of work and/or materials having an original contract value that exceeds ten percent of the amount of the original contract.

**Materials:** Any substance specified in the project, equipment and other material used or consumed in the performance of the work.

**Median:** The portion of a divided highway separating the roadways used by traffic going in opposite directions.

**Method of Measurement:** The manner in which a "Pay Item" is measured to conform to the "Pay Unit."

**Non-Pay Item:** An item of work for which no separate payment will be made under the proposal, but which must be included as an incidental cost for payment on an associated pay item included in the proposal.

**Notice of Award:** A letter from the CITY advising the CONTRACTOR that he is the successful Bidder and the Evans City Council has accepted their proposal.

**Notice to Bidders:** The standard forms inviting proposals or bids.

**Notice to Proceed:** A directive issued by the Engineer, authorizing the CONTRACTOR to start the work or improvements required in the Contract.

**Obligee:** One to whom another is obligated. For bonding purposes, the OWNER is the obligee.

**Open Trench:** The excavated area shall be considered as open trench until all the aggregate base course for pavement replacement has been placed and compacted or, if outside of a pavement area, until the excavated area is brought to finish grade or natural grade.

**Owner:** City of Evans, State of Colorado, acting through its legally constituted officials, officers or employees.

**Pavement:** Any surface of streets, alleys, sidewalks, courts, driveways, etc., consisting of mineral aggregate bound into a rigid or semi-rigid mass by a suitable binder such as, but not limited to, Portland cement or asphalt cement.

**Pavement Structure:** The combination of sub-base, base course, and surface course placed on a sub-grade to support the traffic load and distribute it to the roadbed.

**Pay Item:** A detail of work for which individual payments are to be made under the Contract, as specified in the proposal.

**Payment Bond:** The security provided by the CONTRACTOR solely for the protection of claimants, supplying labor and materials to the CONTRACTOR or its Subcontractors.

**Performance Bond:** The security by the CONTRACTOR solely for the protection of the Contracting Agency and conditioned upon the faithful performance of the contract in accordance with the contract documents, drawings, specifications and conditions thereof.

**Permit:** The license to do construction in public rights-of-way and/or easements; issued by an Agency to a CONTRACTOR working for another party.

**Plans:** All approved drawings or reproductions thereof pertaining to the work and details therefor, which are made a part of the Project Manual and Contract Documents.

**Plant:** The Contractors' and/or subcontractors' facilities, including but not limited to small tools and mobile equipment, located on and/or offsite, necessary for preparation of materials and prosecution of work for the project.

**Principal:** The individual, firm or corporation primarily liable on an obligation, as distinguished from a surety.

**Profile Grade:** The trace of a vertical plane intersecting the top surface of the proposed wearing surface, usually along the longitudinal centerline of the roadbed. Profile grade means either elevation or gradient of such trace according to the context.

**Project:** A specific coordinated construction or similar undertaking identified by a single project number and bid and awarded as one contract. On occasion two or more projects may be bid and awarded as a single contract.

**Project Manual:** All the integral documents of the contract including but not limited to, Contract Documents, General Conditions, Supplemental Conditions, Specifications and drawings.

**Project Supplemental Conditions:** See definition for Supplemental Conditions.

**Proposal:** The offer of a bidder on the prescribed form, to perform the work and to furnish the labor and materials at the prices quoted.

**Proposal Form:** The approved form on which the Contracting Agency requires bids to be prepared and submitted for the work.

**Proposal Guarantee:** The security furnished with a bid to guarantee that the bidder will enter into the contract if their bid is accepted.

**Proposal Pamphlet:** The book or pamphlet pertaining to a specific project, containing

proposal forms, special provisions and other information necessary for and pertinent to the preparation of the proposal or bid.

**Referred Documents:** On all work authorized by the Contracting Agency, any referenced documents in the specification, i.e., Bulletins, Standards, Rules, Methods of Analysis or test. Codes and Specifications of other Agencies, Engineering Societies or Industrial Associations, refer to the Latest Edition thereof, including Amendments, which are in effect and published at the time of Advertising for Bids or the issuing of a permit for the work, unless otherwise stated.

**Resident Project Representative:** The authorized representative of ENGINEER who may be assigned to the site or any part thereof. Also called the Inspector.

**Reasonably Close Conformity:** Compliance with reasonable and customary manufacturing and construction tolerances where working tolerances are not specified. Where working tolerances are specified, reasonably close conformity means compliance with such working tolerances.

**Right-of-Way:** A general term denoting, land, property or interest therein, usually in a strip, acquired for or devoted to a street, highway, or other public improvement.

**Road:** A general term denoting a public way for purposes of vehicular travel, including the entire area within the right-of-way.

**Roadside:** A general term denoting the area adjoining the outer edge of the roadway. Extensive areas between the roadways of a divided highway may also be considered roadside.

**Roadside Development:** Those items necessary to the complete roadway that provide for the preservation of landscape materials and features; the rehabilitation and protection against erosion of all areas disturbed by construction through seeding, sodding, mulching and the placing of other ground covers; such suitable planting and other improvements as may increase the effectiveness and enhance the appearance of the roadway.

**Roadway:** The portion of the right-of-way intended primarily for vehicular traffic and including all appurtenant structures and other features necessary for proper drainage and protection. Where curbs exist, it is that portion of roadway between the faces of the curbs.

**Salvageable Material:** Material that can be saved or salvaged. Unless designated or directed by the ENGINEER or shown on the drawings, all salvageable material shall remain the property of the CONTRACTOR.

**Sewers:** Conduits and related appurtenances employed to collect and carry off water and waste matter to a suitable point of final discharge.

**Shop Drawings:** Drawings or reproduction of drawings, detailing; fabrication and erection of structural elements, falsework and forming for structures, fabrication of reinforcing steel, installed equipment and installation of systems, or any other supplementary drawings or similar data, which the CONTRACTOR is required to submit

for approval.

**Shoulder:** The portion of the roadway contiguous with the traveled way for accommodation of stopped vehicles, for emergency use, and for lateral support of base and surface courses.

**Sidewalk:** That portion of the roadway primarily constructed for the use of pedestrians.

**Supplemental Conditions:** The special conditions, requirements, additions, and/or revisions to the General Conditions and Standard Specifications, applicable to the work, to cover conditions or requirements peculiar to the project under consideration. Supplemental Conditions fall within one of the two following categories and take precedence over the General Conditions.

(a) Project Special Conditions. Special Conditions peculiar to the project and not otherwise thoroughly nor appropriately set forth in the general conditions or standard specifications or drawings.

(b) Standard Special Conditions. Special directions or requirements not otherwise thoroughly or appropriately set forth in the standard specifications, and which are peculiar to a selected group of projects or which are intended for temporary use.

**Specifications:** The descriptions, directions, provisions, and requirement for performing the work as contained in the Contract Documents.

**State:** The State of Colorado.

**Standard Details:** Uniform detail drawings of structures or devices adopted as Standard Details by the ENGINEER.

**Standard:** Uniform general specifications adopted as Standard Specifications by the ENGINEER.

**Storm Drain:** Any conduit and appurtenance intended for the reception and transfer of stormwater.

**Street:** Streets, avenues, alleys, highways, crossings, lanes, intersections, courts, places, and grounds now open or dedicated or hereafter opened or dedicated to public use and public ways.

**Structures:** Bridges, culverts, catch basins, drop inlets, retaining walls, cribbing, manholes, endwalls, sewers, service pipes, underdrains, foundation drains, fences, swimming pools, and other features which may be encountered in the work and not otherwise classed herein.

**Sub-base:** The lower course of the base of a roadway, immediately above the sub-grade.

**Subcontractors:** Those having direct contracts with the CONTRACTOR and those who furnish material worked into a special design according to the Drawings and

Specifications for the work, but not those who merely furnish material not so worked.

**Sub-grade:** The supporting structures on which the pavement and its special undercourses rest.

**Substantial Completion:** The work (or a specified part thereof) has progressed to the point where, in the opinion of ENGINEER and OWNER as evidenced by a letter of Substantial Completion, it is sufficiently complete, in accordance with the Contract Documents, so that the Work (or specified part) can be utilized for the purposes for which it was intended. The terms "substantially complete" and "substantially completed" as applied to any work refer to Substantial Completion thereof. The work must meet the following criteria for Substantial Completion to apply:

- A. At least 90% of all pay items have been completed and are eligible for payment.
- B. The facilities constructed by CONTRACTOR are ready for use.
- C. All traffic features have been completed.
- D. A list of incomplete work items has been issued by the OWNER or ENGINEER to the CONTRACTOR and the CONTRACTOR has accepted and acknowledges the list.

**Substructure:** All of that part of the structure or building below the bearings of simple and continuous spans, skewbacks of arches and tops of footings of rigid frames, together with the backwalls, wingwalls, and wing protection railings.

**Superintendent:** The Contractor's authorized representative in responsible charge of the work.

**Superstructure:** The entire structure or building except the substructure.

**Supplemental Specifications:** Additions and revisions to the Standard Specifications that are adopted subsequent to issuance of the printed Project Manual.

**Surety:** The individual, firm or corporation, bound with and for the CONTRACTOR for the acceptable performance, execution, and completion of the work, and for the satisfaction of all obligations incurred.

**Surface Course:** The finish or wearing course of an asphalt concrete pavement structure.

**Title or Headings:** The titles or headings or the sections and subsections herein are intended for convenience of reference and shall not be considered as having any bearing on their interpretation.

**Township, City, Town or District:** A subdivision of the COUNTY used to designate or identify the location of the proposed work.

**Traveled Way:** The portion of the roadway for the movement of vehicles, exclusive of shoulders and auxiliary lanes.

**Utility:** Pipelines, conduits, ducts, transmission lines, overhead or underground wires, railroads, storm drains, sanitary sewers, irrigation facilities, street lighting traffic signals, and fire alarm systems, and appurtenances of public utilities and those of private industry, businesses or individuals solely for their own use or use of their customers which are operated or maintained in, on, under, over or across public right-of-way or public or private easement.

**Waterworks (Water Supply System):** The reservoirs, pipe lines, wells, pumping equipment, purification works, mains, service pipes, and all related appliances and appurtenances utilized in the procurement, transportation and delivery of an adequate, safe, and palatable water supply for the Contracting Agency.

**Work:** Any or all of the improvements mentioned and authorized to be made, and the construction, demolition, reconstruction, and repair of all or any portion of such improvements, and all labor, services, incidental expenses, and material necessary or incidental thereto.

**Working Day:** A calendar day, exclusive of Saturdays, Sundays and Contracting Agency recognized legal holidays, on which weather and other conditions not under the control of the CONTRACTOR will permit construction operations to proceed for the major part of the day with the normal working force engaged in performing the controlling item or items of work which would be in progress at that time.

## **2.2 GENERAL CONTRACT REQUIREMENTS**

### **2.2.1 FAMILIARITY WITH WORK**

The CITY has endeavored to ascertain all pertinent information regarding site conditions, and subsurface conditions, and has, to the best of their ability, furnished all such information to the CONTRACTOR. Such information is given, however, as being the best factual information available to the CITY, but is advisory only. The CONTRACTOR, by careful examination, shall satisfy itself as to the nature and location of the work, the character of equipment and facilities needed preliminary to and during the prosecution of the work, the general and local conditions, and all other matters that can in any way affect the work under this Contract.

Bidder shall examine the site of the proposed work and all documents pertaining to the work. It is mutually agreed that the submission of a proposal shall be considered prima facie evidence that the bidder has made such examination and is familiar with the character, quality and quantity of the work to be performed and material to be furnished.

Logs of test hole, ground water levels, and any accompanying soil reports as furnished by the Contracting Agency are furnished for general information only. The field condition so set forth shall not constitute a representation or warranty, expressed or implied, that such conditions are existent. Bidders shall make their own investigations and form their own estimates of the site conditions. After the submission of the proposal, no complaint or claim that there was any misunderstanding as to the quantities, conditions or nature of the work will be entertained.

### **2.2.2 CHANGED CONDITIONS**

The CONTRACTOR shall promptly, and before such conditions are disturbed, except in the event of any emergency, notify the CITY in writing of: (1) Subsurface or latent physical conditions at the site differing materially from those indicated in this Contract; or (2), previously unknown physical or other conditions at the site, of an unusual nature, not generally recognized as inherent in work of the character provided for in this Contract. The ENGINEER shall promptly investigate the conditions, and if he finds that such conditions do so materially differ and cause an increase or decrease in the cost of, or the time required for, performance of this Contract, an equitable adjustment shall be made, and the Contract modified in writing accordingly. Any claim of the CONTRACTOR for adjustment hereunder shall not be allowed unless he has given notice as above required, provided that the ENGINEER may, if he determines the facts so justify, consider and adjust any such claims assessed before the date of final settlement of the Contract. If the parties fail to agree upon the adjustment to be made, the dispute shall be determined as provided in Paragraph 2.2.33 hereof.

### **2.2.3 ORDER OF COMPLETION**

The CONTRACTOR shall submit, at such times as may reasonably be requested by the ENGINEER, schedules which shall show the order in which the CONTRACTOR proposes to carry on the work, with dates at which the CONTRACTOR will start the several parts. The special provisions or plans may require that certain phases or parts of the work be completed first or in a certain order. If the CONTRACTOR elects to use PERT or CPM charts, he shall furnish copies of them to the ENGINEER upon request.

#### 2.2.4 DESIGN AND INSTRUCTIONS

It is agreed that the CITY will be responsible for the adequacy of design and Specifications. The CITY, through the ENGINEER, shall furnish Specifications, which adequately represent the requirements of the work to be performed under the Contract. All such instructions shall be consistent with the Contract Documents and shall be true developments thereof. Specifications that adequately represent the work to be done shall be furnished prior to the time of entering into the Contract. The ENGINEER may, during the life of the Contract, and in accordance with Paragraph 2.2.15, issue additional instructions, by means of drawings or other media, necessary to illustrate changes in the work.

#### 2.2.5 SURVEYS

The CITY has provided a suitable number of benchmarks adjacent to the work. From the information provided by the CITY, the CONTRACTOR shall develop and make all detail surveys needed for construction, such as slope stakes, batter boards, stakes for pile locations, and other working points, lines, and elevations. The CONTRACTOR shall be responsible for any mistakes made in its detailed surveys.

The CONTRACTOR shall carefully preserve benchmarks, reference points and stakes, and in case of willful or careless destruction, he shall be charged with the resulting expense and shall be responsible for any mistakes that may be caused by their necessary loss or disturbance.

#### 2.2.6 CLAIMS

If the CONTRACTOR claims that any instructions by drawings or otherwise, issued after the date of the Contract, involve extra cost under the Contract, he shall give the ENGINEER written notice thereof within ten (10) days, after the receipt of such instruction, and in any event before proceeding to execute the work, except emergency endangering life or property, and the procedure shall than be as provided for changes in the work. No such claim shall be valid unless so made.

#### 2.2.7 EXECUTION AND CORRELATION OF DOCUMENTS

The Agreement shall be signed in duplicate by the CITY and the CONTRACTOR.

The Contract Documents are complimentary and what is called for by anyone shall be as binding as if called for by all. In case of conflict between Drawings and Specifications, the Specifications shall govern. Special Specifications shall govern over Standard Specifications. Materials or work described in words which so applied have a well-known technical or trade meaning shall be held to refer to such recognized standards.

#### 2.2.8 MATERIALS AND APPLIANCES

Unless otherwise stipulated, the CONTRACTOR shall provide and pay for all materials, labor, water, tools, equipment, light, power, transportation and other facilities necessary for the execution and completion of work. The CONTRACTOR shall, if required, furnish satisfactory evidence as to the kind and quality of materials.

#### 2.2.9 EMPLOYEES

The CONTRACTOR shall, at all times, enforce strict discipline and good order among its employees, and shall seek to avoid employing, for the Contract, any unfit person or anyone not skilled in the work assigned to them.

Adequate sanitary facilities shall be provided by the CONTRACTOR.

Employees of the CONTRACTOR and/or any subcontractor working on the project shall not be considered as employees of the City of Evans, nor shall they be entitled to any of the benefits provided to City of Evans employees.

#### 2.2.10 ROYALTIES AND PATENTS

The CONTRACTOR shall pay all applicable royalties and license fees. He shall defend all suits or claims for infringement for any patent rights and save the CITY harmless from loss on accounts thereof, except that the CITY shall be responsible for any such loss when a particular process, design, or the product of a particular manufacturer or manufacturers is specified, unless the CITY has notified the CONTRACTOR prior to the signing of the Contract that the particular process, design, or product is patented or is believed to be patented.

#### 2.2.11 PERMITS, LICENSES AND REGULATIONS

Permits and licenses of a temporary nature, necessary for the prosecution of the work, shall be secured and paid for by the CONTRACTOR. Permits, licenses and easements for permanent structures or permanent changes in existing facilities shall be secured and paid for by the CITY, unless otherwise specified.

The CONTRACTOR shall give all notices and comply with all laws, ordinances, rules and regulations bearing on the conduct of the work as drawn and specified. If the CONTRACTOR observes that the Specifications are at variance therewith, he shall promptly notify the ENGINEER in writing, and any necessary changes shall be adjusted in the Contract for changes in the work.

#### 2.2.12 INSPECTION OF WORK

All materials and equipment used in the construction of the project shall be subject to adequate testing in accordance with generally accepted standards as required by the Contract Documents.

The CITY shall provide sufficient competent personnel, working under qualified supervision for the inspection of the work, while such work is in progress, to ascertain that the completed work will comply in all respects with the standards and requirements set forth in the Specifications. The inspection of the Contract will be as it relates to the compliance with the Specifications, quality of workmanship, and material. Notwithstanding such inspection, the CONTRACTOR will be held responsible for the acceptability of the work.

The ENGINEER and its representatives shall, at all times, have access to work whenever it is in preparation or progress, and the CONTRACTOR shall provide proper facilities for such access and for inspection.

If the Specifications, the ENGINEER's instructions, laws, ordinances, or any public authority require any work to be specially tested or approved, the CONTRACTOR shall give the ENGINEER timely notice to its readiness for inspection, and if the inspection is by an authority other than the ENGINEER, a date shall be fixed for such an inspection. Inspections by the ENGINEER shall be promptly made, and where applicable, at the source of supply. Any work required by the ENGINEER to be uncovered for examination shall be properly restored at the CONTRACTOR's expense unless the ENGINEER has unreasonably delayed inspection.

Re-examination of any work may be ordered by the ENGINEER, and if so ordered, the work must be uncovered by the CONTRACTOR. If such work is found to be in accordance with the Contract Documents, the CITY shall pay the cost of re-examination. If such work is not in accordance with the Contract Document, the CONTRACTOR shall pay such cost.

#### 2.2.13 SUPERINTENDENTS

The CONTRACTOR shall keep on its work at all times during its progress, competent superintendents and/or responsible assistants. The superintendent shall represent the CONTRACTOR and all directions given to them shall immediately be confirmed in writing to the CONTRACTOR. Superintendent shall be named in writing by CONTRACTOR at the beginning of the work.

#### 2.2.14 PRECONTRACT EXAMINATION AND DISCOVERY OF DISCREPANCIES DURING WORK

Before submitting their proposal, the CONTRACTOR will examine all construction plans and the entire and complete specifications. The CONTRACTOR will become well and fully informed as to the materials and the character of the work required, the relationship of all the particular parts of the work, and he will visit and inspect the site, observing and examining the conditions existing.

After the execution of the Contract, no consideration will be granted for any misunderstanding of the materials to be furnished or the work to be done, it being mutually understood that the tender of the proposal carried with it an agreement to this end and all other conditions mentioned in the Contract and the Specifications, and implied a full and complete understanding of them and all construction plans, drawings, notes, indications, and requirements.

Should anything be omitted from the construction plans or specifications necessary to the proper completion of the work herein described, it shall be the duty of the CONTRACTOR to so notify the CITY before signing the Contract, and in the event of failure of the CONTRACTOR to give such notice, they shall make good any damage or defect in its work caused thereby without extra charge. No allowance will be made for lack of full knowledge of all conditions, except such underground conditions as are determined after commencement of the work and were unknown to the CONTRACTOR.

If the CONTRACTOR, in the course of the work, finds any discrepancy between the Specifications and the physical conditions of the locality, or any errors or omissions in the layout as given by survey points and instruction, he shall immediately inform the ENGINEER, in writing, and the ENGINEER shall promptly verify the same. Any work done after such discovery, until authorized, will be done at the CONTRACTOR's risk, except in the event of an emergency.

#### 2.2.15 CHANGES IN THE WORK

At any time by written order, the CITY may make changes in the Specifications or scheduling of the Contract within the general scope. All such work shall be executed under the time constraints of the original contract except that any claim for extension of time caused thereby shall be allowed and adjusted at the time of ordering such change or at such time as it can be ascertained.

In giving instruction, the ENGINEER shall have authority to make minor changes in the work not involving extra cost, and not inconsistent with the purpose of the work. Except in an emergency endangering life and property, no claim for an addition to the contract sum shall be valid unless

the additional work was so ordered by the ENGINEER.

The CONTRACTOR shall proceed with the work as changed and the value of any such work or change shall be determined as provided for in the Agreement herein.

The CITY may at any time, as the need arises, order changes within the scope of the work without invalidating the Agreement. If such changes increase or decrease the amount due under the Contract Documents, or in the time required for performance of the work, the CONTRACTOR shall perform the same at the unit prices or lump sum indicated in the bid. Changes may occur to a maximum of twenty-five percent (25%) of the contract price. After exceeding twenty-five percent (25%), the applicable unit price or lump sum may be negotiable, and an equitable adjustment shall be authorized by change order.

#### 2.2.16 EXTENSION OF TIME

- A. Extension of time stipulated in the Contract for completion of the work will be made when changes in the work occur, as provided in Paragraph 2.2.15; when the work is suspended as provided in Paragraph 2.2.17; and when the work of the CONTRACTOR is delayed on account of conditions which could not have been foreseen, or which were beyond the control of the CONTRACTOR, their subcontractors or suppliers, and which were not the result of their fault or negligence.

Extension of time for completion shall also be allowed for any delays in the progress of the work that in the opinion of the ENGINEER entitles the CONTRACTOR to an extension of time.

- B. The CONTRACTOR shall notify the ENGINEER promptly of any occurrence or condition which in the CONTRACTOR's opinion entitles them to an extension of time. Such notice shall be in writing and shall be submitted in ample time to permit full investigation and evaluation of the CONTRACTOR's claim. Failure to provide such notice shall constitute a waiver by the CONTRACTOR of any claim.

#### 2.2.17 SUSPENSION OF WORK

The CITY may at any time suspend the work, or any part thereof, by giving three (3) days' notice to the CONTRACTOR in writing.

#### 2.2.18 THE CITY'S RIGHT TO TERMINATE CONTRACT

If the CONTRACTOR should be adjudged bankrupt, or if they should make a general assignment for the benefit of their creditors, or if a receiver should be appointed as a result of their insolvency, or if he should persistently or repeatedly refuse or should fail, except for cases in which extensions of time are provided, to supply enough properly-skilled workmen or materials, or if he should fail to make payments to subcontractors or for materials or labor so as to affect the progress of the work or persistently be guilty of a substantial violation of the Contract, then the CITY, upon written notice from the ENGINEER that sufficient cause exists to justify such action and without prejudice to any other right or remedy, and after giving the CONTRACTOR and its Surety seven (7) days' written notice, terminate the employment of the CONTRACTOR and take possession of the premises and of all materials, tools, equipment and other facilities installed on the work and paid for by the CITY, and finish the work by whatever method the ENGINEER may be deem expedient. In such case, the CONTRACTOR shall not be entitled to receive any further payment until the work is finished. If the unpaid balance of the contract price shall exceed the expense of finishing the work, including compensation for additional managerial and administrative services, such excess shall be paid to the CONTRACTOR. If such expense shall exceed such unpaid balance, the CONTRACTOR shall pay the difference to the CITY. The expense incurred by the CITY as herein provided, and the damage incurred through the CONTRACTOR's default, shall be certified by the ENGINEER.

Where the Contract has been terminated by the CITY, said termination shall not affect or terminate any of the rights of the CITY then existing or which may thereafter accrue because of such default as against the CONTRACTOR or their Surety. Any retention or payment of moneys by the CITY due to the CONTRACTOR under the terms of the Contract, shall not release the CONTRACTOR or their Surety from liability for the CONTRACTOR's default.

#### 2.2.19 CONTRACTOR'S RIGHT TO STOP WORK OR TERMINATE CONTRACT

If the work should be stopped under an order of any court, or other public authority, for a period of more than three (3) months, through no act or fault of the CONTRACTOR, the CITY will pay an amount not to exceed 50% of an undisputed sum within forty-five (45) days of its maturity and presentation, then the CONTRACTOR may, upon seven (7) days' written notice to the ENGINEER, stop work or terminate this Contract and recover from the CITY payment for all work executed, plus any loss sustained upon any plant or materials, plus reasonable profit and damages.

#### 2.2.20 CANCELLATION OF CONTRACT

Failure of the CONTRACTOR to comply with any of the requirements of the Contract and the Specifications may be considered as evidence of the inability on the part of the CONTRACTOR to maintain the quality and service standards deemed necessary and shall be sufficient cause for the cancellation of the Agreement and the initiating of legal action against the Performance Bond of the CONTRACTOR.

#### 2.2.21 CORRECTION OF WORK BEFORE FINAL PAYMENT

The CONTRACTOR shall promptly remove from the premises all materials and work condemned by the ENGINEER as failing to meet contract requirements, whether incorporated in the work or not, and the CONTRACTOR shall promptly replace and re-execute its own work in accordance with the Contract and without expense to the CITY and shall bear the expense of making good all work of other CONTRACTORS destroyed or damaged by such removal or replacement.

All removal and replacement work shall be done at the CONTRACTOR's expense. If the CONTRACTOR does not take action to remove such condemned work and materials within ten (10) days after written notice, the CITY may remove them and store the material at the expense of the CONTRACTOR. If the CONTRACTOR does not pay the expense of such removal and storage within ten (10) days' time thereafter, the CITY may, upon ten (10) days' written notice, sell such materials at auction or at private sale and shall pay the CONTRACTOR any net proceeds thereof, after deducting all costs and expenses that should have been borne by the CONTRACTOR.

#### 2.2.22 REMOVAL OF EQUIPMENT

In the case of termination of this Contract before completion for whatever cause, the CONTRACTOR, if notified to do so by the CITY, shall promptly remove any part or all of its equipment and supplies from the property of the CITY, failing which, the CITY shall have the right to exercise control over and to remove such equipment and supplies at the expense of, and without recourse, by the CONTRACTOR.

#### 2.2.23 RESPONSIBILITY FOR WORK

The CONTRACTOR assumes full responsibility for the work. Until final acceptance, the CONTRACTOR shall be responsible for damage to or destruction of the work, except for any part covered by partial acceptance as set forth in Paragraph 2.2.24 and except such damage or destruction that is caused by the negligent or willful acts of the CITY.

#### 2.2.24 PARTIAL COMPLETION AND ACCEPTANCE

If at any time prior to the issuance of the final certificate, referred to in Paragraph 2.2.34 hereinafter, any portion of the permanent construction has been satisfactorily completed to the ENGINEER's satisfaction, and if the ENGINEER determines that such portion of the permanent construction is not required for the operations of the CONTRACTOR, but is needed by the CITY, the ENGINEER shall issue to the CONTRACTOR a Certificate of Partial Completion, and thereupon or at any time thereafter, the CITY may take over and use the portion of the permanent construction described in such certificate.

The issuance of a Certificate of Partial Completion shall not be construed to constitute an extension of the CONTRACTOR's time to complete the portion of the permanent construction to which it relates, if he fails to complete it in accordance with the terms of this Contract. The issuance of such a certificate shall not operate to release the CONTRACTOR or their Sureties from any obligations under this Contract or the Performance Bond.

If such prior use increases the cost of or delays the work, the CONTRACTOR shall be entitled to extra compensation, or extension of time, or both, as the ENGINEER may determine, unless otherwise provided.

#### 2.2.25 PAYMENT WITHHELD PRIOR TO FINAL ACCEPTANCE OF WORK

As a result of subsequently discovered evidence, the CITY may withhold or nullify the whole or part of any certificate of payment to such extent as may be necessary to protect itself from loss occasioned by:

- A. Defective work not remedied by the CONTRACTOR
- B. Claims filed or reasonable evidence indicating probable filing of claims by other parties against the CONTRACTOR for work done on the project

- C. Failure of the CONTRACTOR to make payments properly to subcontractors or for material or labor
- D. Damage by the CONTRACTOR to subcontractors or to another contractor

When the above grounds are removed, or the CONTRACTOR provides Surety Bond satisfactory to the CITY that will protect the CITY in the amount withheld, payment shall be made for amounts withheld because of them. No moneys may be withheld under (b) and (c) if a Payment Bond is included in the Contract.

#### 2.2.26 CONTRACTOR'S INSURANCE AND INDEMNIFICATION

The CONTRACTOR shall secure and maintain such insurance policies as will protect itself, its subcontractors, and City of Evans, its employees and agents, from claims for bodily injuries, death, or property damage, which may arise from operations under this Contract, whether such operations be by itself or by any subcontractor or anyone employed by them directly or indirectly. The following insurance policies are required and must be evidenced by Certificates of Insurance:

- A. Statutory Workers' Compensation
- B. Commercial General Liability
 

General Aggregate	\$2,000,000
Products/	\$2,000,000
(Completed Operations Aggregate)	
Each Occurrence	\$1,000,000
Personal & Advertising Injury	\$1,000,000
Fire Damage	\$ 50,000
Medical Expense	\$ 5,000
- C. Automobile Liability
 

Bodily Injury and Property Damage	\$ 1,000,000
(Combined Single Limit)	
- D. Builders Risk/Installation Floater Full Replacement Cost

Be written on a Builder's Risk "All-Risk" or on Peril or Special Causes of Loss policy form that shall at least include insurance for physical loss and damage to the Work, temporary buildings, false work, and Work in transit and shall insure against at least the following perils: fire, lightning, extended coverage, theft, vandalism and malicious mischief, collapse, debris removal, demolition occasioned by enforcement of laws and regulations, water damage.

Certificates of Insurance must show "City of Evans, its employees and agents" as an Additional Insured.

All policies shall be for not less than the amount set forth above or as stated in the Special Conditions. Other forms of insurance shall also be provided if called for by the Special

Conditions.

All Certificates of Insurance must be filed with the ENGINEER along with the Performance and Payment Bonds and shall be subject to their approval as to adequacy of protection, within the requirements as stated herein. Said Certificates of Insurance shall contain a thirty (30) days' written notice of cancellation in favor of the CITY.

The CITY cannot and by this Agreement does not agree to indemnify, hold harmless, exonerate or assume the defense of the CONTRACTOR or any other person or entity whatsoever, for any purpose whatsoever. To the extent allowable under C.R.S. Section 13-50.5-102(8), the CONTRACTOR shall defend, indemnify and hold harmless the CITY, its mayor and City council, officials, officers, directors, agents and employees from any and all claims, demands, suits, actions or proceedings of any kind or nature whatsoever, including worker's compensation claims, to the extent resulting from the fault of, or negligent services rendered by the CONTRACTOR, its employees, agents or subconsultants, or others for whom the CONTRACTOR is legally liable, under this Agreement; provided, however, that the CONTRACTOR need not indemnify or save harmless the CITY, its mayor and City council, its officers, agents and employees from damages resulting from the sole negligence of the City's mayor and City council, officials, officers, directors, agents and employees."

All insurance and bonding companies providing coverage or surety under this contract shall have a Best Insurance Rating of "A" or better.

#### 2.2.27 SURETY BONDS

The CITY shall have the right, prior to the signing of the Contract, to require the CONTRACTOR to furnish Payment and Performance Bonds in such form as the CITY may prescribe in the bidding documents and executed by one or more financially responsible Sureties licensed to do business in the State of Colorado. The premiums for said Bonds shall be paid by the CONTRACTOR. Such Bonds shall cover the entire Contract amount, regardless of changes therein, shall remain in full effect for a period of one year from the date of issuance of a Certificate of Completion, and shall be filed with the ENGINEER prior to the commencement of any work on the project.

#### 2.2.28 CONTRACTOR'S INSURANCE

The CONTRACTOR shall secure and maintain insurance to one hundred percent (100%) of the insurable value of the entire work in the Contract and any structures attached or adjacent thereto against fire, earthquake, flood, and other perils as he may deem necessary and shall name the CITY and subcontractors as Additional Insured.

All insurance and bonding companies providing coverage or surety under this contract shall have a Best Insurance rating of "A" or better.

#### 2.2.29 ASSIGNMENT

Neither party to the Contract shall assign the Contract or sublet it as a whole without the written consent of the other and its Surety, nor shall the CONTRACTOR assign any moneys due or to become due to them hereunder, except to a bank or financial institution acceptable to the CITY.

#### 2.2.30 RIGHTS OF VARIOUS INTERESTS

Wherever work being done by the CITY's forces, utility companies, or by other CONTRACTOR's forces is contiguous to work covered by this Contract, the respective rights of the various interest invoiced shall be established by the ENGINEER, to secure the completion of the various portions of the work in general harmony.

- A. Before issuance of final payment, the CONTRACTOR, if required in the Special Conditions, shall certify in writing to the ENGINEER that all payrolls, material bills, and other indebtedness connected with the work, have been paid or otherwise satisfied. If the Contract does not include a payment Bond the CONTRACTOR may submit, in lieu of certification of payment, a Surety Bond in the amount of the disputed indebtedness or liens, guaranteeing payment of all such disputed amounts, including all related costs and interest in connection with said disputed indebtedness or liens, which the CITY may be compelled to pay upon adjudication.
- B. The making and acceptance of the final payment shall constitute a waiver of all claims by the CITY, other than those arising from unsettled liens, from faulty work appearing within the guarantee period, provided in the Special Conditions, from the requirements of the Drawings and Specifications, or from manufacturer's guarantees. It shall also constitute a waiver of all claims by the CONTRACTOR, except those previously made and still unsettled.
- C. If after the work has been substantially completed, full completion thereof is materially delayed through no fault of the CONTRACTOR, and the ENGINEER so certifies, the CITY shall, upon certificate of the ENGINEER, and without terminating the Contract, make payment of the balance due for that portion of the work fully and completed and accepted. Such payment shall be made under the terms and conditions governing final payment, except that it shall not constitute a waiver of claims.
- D. If the CITY fails to make payment as herein provided, there shall be added to each payment daily interest at the rate of six percent (6%) per annum commencing on the first day after said payment is due and continuing until the payment is delivered or mailed to the CONTRACTOR.

#### 2.2.31 ENGINEER'S STATUS

The ENGINEER shall perform technical inspection of the work. He has authority to stop the work whenever such stoppage may be necessary to insure the proper execution of the Contract. He shall also have authority to reject all work and materials which do not conform to the Contract and to decide questions which arise in the execution of the work.

#### 2.2.32 ENGINEER'S DECISIONS

The ENGINEER shall, within a reasonable time after their presentation to them, make decisions in writing on all claims of the CONTRACTOR and on all other matters relating to the execution and progress of the work or the interpretation of the Contract Documents.

### 2.2.33 ARBITRATION

Any controversy or claim arising out of or relating to this Contract, or the breach thereof, which cannot be resolved by mutual agreement, shall be settled by arbitration in accordance with the Rules of the American Arbitration Association, and judgment upon the award rendered by the Arbitrator(s) may be entered in any court having jurisdiction thereof.

### 2.2.34 ACCEPTANCE AND FINAL PAYMENT

Upon receipt of written notice that the work is substantially complete or ready for final inspection and acceptance, the ENGINEER will promptly make such inspection and when he finds the work acceptable under the Contract and the Contract fully performed or substantially completed, they shall promptly issue a certificate, over their own signature, stating that the work required by this Contract has been substantially completed and is accepted by them under the terms and conditions thereof, and the entire balance found to be due the CONTRACTOR, including the retained percentage, unless a retention based on the ENGINEER's estimate of the fair value of the claims against the CONTRACTOR and the cost of completing the uncompleted or unsatisfactory items of work with specified amounts for each incomplete or defective item of work, is due and payable. No final payment shall be made by the CITY unless and until the CONTRACTOR has certified in writing to the ENGINEER that all payroll, material bills, and other indebtedness connected with the work have been paid or otherwise satisfied.

The CONTRACTOR shall cause appropriate provisions to be inserted in all subcontracts relative to the project to bind the subcontractors to the CONTRACTOR by the terms of the Contract Documents, and to give the CONTRACTOR the same power as regard to terminating any subcontract that the CITY may exercise over the CONTRACTOR under any provision of the Contract Documents.

Nothing contained in this Agreement shall create any contractual relationship between any subcontractor and the CITY.

Subcontracts, or transfer of Contract, shall not release the CONTRACTOR of its liability under the Contract and Bonds.

### 2.2.35 LIQUIDATED DAMAGES

The CONTRACTOR agrees that he can and will complete the project within the prescribed time limit as stated in Article 1.5.9 (Notice to Proceed) and within the time as may be extended. In the event the CONTRACTOR fails to complete the work within the allotted time limit, the following liquidated damages will be applied:

From More Than	Original Contract Amount to And Including	Daily Charge
\$ 0	\$ 25,000	\$ 85
25,000	50,000	140
50,000	100,000	205
100,000	500,000	280
500,000	1,000,000	420
1,000,000	2,000,000	560
2,000,000	4,000,000	840
4,000,000	8,000,000	1,120

8,000,000

10,000,000

1,400

These rates will be assessed per calendar day for each day which the CONTRACTOR fails to finish the work in excess of the time period allotted. The parties agree that the liquidated damages, as stated herein, are not a penalty and are reasonable, given the expected harm from a delay in completion, the difficulty of proving actual loss, and the inadequacy of any other remedy.

#### 2.2.36 ADVANCE NOTICE

It shall be the responsibility of the CONTRACTOR to notify the ENGINEER or inspector sufficiently in advance of its operations to enable the ENGINEER or inspector to set the required control stakes and marks.

In order to assure proper availability of construction supervision or other personnel from the ENGINEER's staff, the following notices will be required as minimums:

- A. One (1) week notice for major additions or modifications to construction staking.
- B. Two (2) working days' notice for all staking except for emergencies.
- C. Two (2) days' written notice shall be delivered to the ENGINEER or inspector prior to any work done on Saturday, Sunday, nights, and legal holidays.

The failure of the CONTRACTOR to provide minimum notices will not be considered for time extensions or extra compensations.

#### 2.2.37 WORK DONE WITHOUT LINES OR GRADES

Any work done without having been properly located and established as determined by the Engineer may be ordered removed and replaced at the CONTRACTOR's expense.

#### 2.2.38 TAXES

Except as may be otherwise provided in this Contract, the contract price is to include all applicable taxes, but does not include any tax from which the CITY and the Contractor are exempt. Upon request by the CONTRACTOR, the CITY shall furnish a tax exemption certificate or similar evidence of exemption with respect to any such tax not included in the contract price, pursuant to this provision.

### 2.3 LEGAL RELATIONS & RESPONSIBILITIES TO PUBLIC

#### 2.3.1 LEGAL RELATIONS AND RESPONSIBILITY TO PUBLIC

Laws and Regulations: The CONTRACTOR shall keep itself fully informed of all city and county ordinances and regulations, and state and federal laws which in any manner affect the work herein specified. He shall, at all times, observe and comply with said ordinances, regulations, or laws, caused by the negligent actions of the CONTRACTOR, its agent, or employees.

### 2.3.2 PROJECT SAFETY

The CONTRACTOR is solely responsible for and shall take reasonable precautions in the performance of the work under this Contract to protect all persons from hazards to life and property. The CONTRACTOR shall comply with all health, safety and fire protection regulations and requirements.

### 2.3.3 PROTECTION OF THE PUBLIC AND OF WORK AND PROPERTY

The CONTRACTOR shall provide and maintain all necessary watchmen, barricades, warning lights, and signs in accordance with the Manual of Uniform Traffic Control Devices and take all reasonable precautions for the protection and safety of the public. He shall continuously maintain reasonable protection of all work from damage, and shall take all reasonable precautions to protect the CITY's property from injury or loss arising in connection with this Contract. Streets and highways shall be kept free of dirt and litter from CONTRACTOR's handling operations. The CONTRACTOR shall take reasonable precautions to protect private property adjacent to the project from such nuisances as dust and dirt, rock, and excessive noise. They shall make good any damage, injury or loss to their work and to the property owner resulting from lack of reasonable protective precautions, except such as may be due to errors in the Contract Documents or caused by agents of adjacent private and public property, as provided by law and the Contract Documents.

### 2.3.4 EQUAL OPPORTUNITY

During the performance of this contract, the contractor agrees as follows:

- A. The contractor will not discriminate against any employee or applicant for employment because of race, color, religion, sex, or national origin. The contractor will take affirmative action to ensure that applicants are employed, and that employees are treated during employment without regard to their race, color, religion, sex, or national origin. Such action shall include, but not be limited to the following: Employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The contractor agrees to post in conspicuous places, available to employees and applicants for employment, notices to be provided setting forth the provisions of this nondiscrimination clause.
- B. The contractor will, in all solicitations or advertisements for employees placed by or on behalf of the contractor, state that all qualified applicants will receive considerations for employment without regard to race, color, religion, sex, or national origin.
- C. The contractor will send to each labor union or representative of workers with which he has a collective bargaining agreement or other contract or understanding, a notice to be provided advising the said labor union or workers' representatives of the contractor's commitments under this section and shall post copies of the notice in conspicuous places available to employees and applicants for employment.
- D. The contractor will comply with all provisions of Executive Order 11246 of September 24, 1965, and of the rules, regulations, and relevant orders of the Secretary of Labor.

- E. The contractor will furnish all information and reports required by Executive Order 11246 of September 24, 1965, and by rules, regulations, and orders of the Secretary of Labor, or pursuant thereto, and will permit access to his books, records, and accounts by the administering agency and the Secretary of Labor for purposes of investigation to ascertain compliance with such rules, regulations, and orders.
- F. In the event of the contractor's noncompliance with the nondiscrimination clauses of this contract or with any of the said rules, regulations, or orders, this contract may be canceled, terminated, or suspended in whole or in part and the contractor may be declared ineligible for further Government contracts or federally assisted construction contracts in accordance with procedures authorized in Executive Order 11246 of September 24, 1965, and such other sanctions may be imposed and remedies invoked as provided in Executive Order 11246 of September 24, 1965, or by rule, regulation, or order of the Secretary of Labor, or as otherwise provided by law.
- G. The contractor will include the portion of the sentence immediately preceding paragraph (1) and the provisions of paragraphs (1) through (7) in every subcontract or purchase order unless exempted by rules, regulations, or orders of the Secretary of Labor issued pursuant to section 204 of Executive Order 11246 of September 24, 1965, so that such provisions will be binding upon each subcontractor or vendor. The contractor will take such action with respect to any subcontract or purchase order as the administering agency may direct as a means of enforcing such provisions, including sanctions for noncompliance: Provided, however, That in the event a contractor becomes involved in, or is threatened with, litigation with a subcontractor or vendor as a result of such direction by the administering agency the contractor may request the United States to enter into such litigation to protect the interests of the United States."

## **2.4 MATERIALS & WORKMANSHIP**

### **2.4.1 GUARANTEES**

The CONTRACTOR shall guarantee its work against defective materials or workmanship for a period of two (2) years from the date of initial acceptance.

Contractor warrants and guarantees to the CITY that all equipment and materials furnished under this Contract are free from all defects in workmanship and materials.

Contractor shall remove from the project area all work or materials rejected by the CITY or its inspector for failure to comply with the Contract Documents, whether incorporated in the construction or not. The CONTRACTOR shall promptly replace the materials or re-execute the work in accordance the Contract Documents and without expense to the CITY which are or become defective due to such defects within two (2) years after the date of receipt by the CITY. The CONTRACTOR shall also bear the expense of making good all work of other contractors destroyed or damaged by such removal or replacement.

#### 2.4.2 WARRANTIES

The CONTRACTOR shall guarantee its work against defective materials and workmanship for a period of two (2) years from the date of initial acceptance.

### 2.5 MEASUREMENT & PAYMENT

#### 2.5.1 PAYMENT

Partial payment under the Contract shall be made at the request of the CONTRACTOR once each month, based upon partial estimates to be furnished by the CONTRACTOR and approved by the CONTRACTOR once each month, based upon partial estimates to be furnished by the CONTRACTOR and approved by the ENGINEER or inspector. In making such partial payment, there shall be retained five percent (5%) of the estimated amounts until final completion and acceptance of all work covered by the Contract.

In preparing estimates for partial payments, the material delivered on the site and preparatory work done may be taken into consideration.

Payments for work under subcontracts of the CONTRACTOR shall be subject to the above conditions applying to the contract after the work under a subcontract has been fifty percent (50%) completed. In preparing estimates for partial payments, the material delivered on the site and preparatory work done may be taken into consideration.

Should the CONTRACTOR fail to proceed properly and in accordance with the Guarantee, the CITY may have such work performed at the expense of the CONTRACTOR.

#### 2.5.2 PAY QUANTITIES

The CONTRACTOR shall be paid on a unit price basis as indicated by the proposal for the actual quantities installed.

### 2.6 SCOPE OF WORK

#### 2.6.1 CHANGES IN THE WORK

At any time by written order, the CITY may make changes in the Drawings and Specifications or scheduling of the Contract within the general scope. All such work shall be executed under the time constraints of the original Contract, except that any claim for extension of time caused thereby shall be allowed and adjusted at the time of ordering such change or at such time as it can be ascertained.

- A. Unit prices previously approved,
- B. An agreed lump sum,
- C. The actual cost of labor, direct overhead, materials, supplies, equipment and other services necessary to complete the work. In addition, there shall be added on an amount to be agreed upon, but not to exceed fifteen percent (15%) of the actual cost of the work, to cover the cost of general overhead and profit.

#### 2.6.2 SUBLETTING OF CONTRACT

The CONTRACTOR shall not sublet, sell, transfer, assign, or otherwise dispose of the Contract, or of their rights, title, or interest therein, without written consent of the CITY. The CONTRACTOR may utilize the services of specialty subcontractors on those parts of the project which, under normal contraction practices, are performed by specialty subcontractors.

The CONTRACTOR shall not award work to subcontractors in excess of fifty percent (50%) of the contract price without prior written approval of the CITY.

The CONTRACTOR shall be as fully responsible to the CITY for the acts and omissions of their subcontractors and of persons directly or indirectly employed by them, as they are for the acts and omissions of persons directly employed by them.

#### 2.6.3 SEPARATE CONTRACTS

The CITY reserves the right to let other contracts in connection with this project. The CONTRACTOR shall afford other contractors reasonable opportunity for the introduction and storage of their materials and the execution of their work and shall properly connect and coordinate its work with theirs. If the proper execution or results of any part of the CONTRACTOR's work depends upon the work of any other contractor, the CONTRACTOR shall inspect and promptly report to the ENGINEER any defects in such work that render it unsuitable for such proper execution and results.

#### 2.6.4 SUBCONTRACTS

The CONTRACTOR shall, as soon as practicable after signing the Contract, but in any event prior to the performance of any work by any subcontractor, notify the CITY, in writing, of the names of the subcontractors proposed for the work, designating the portions of work to be performed by each.

The CONTRACTOR agrees that they are as fully responsible to the CITY for the acts and omissions of their subcontractors and of persons either directly or indirectly employed by them, as they are for the acts and omissions of persons directly employed by them.

Nothing contained in the Contract Documents shall create any contractual relation between any subcontractor and the CITY.

#### 2.6.5 UNDERGROUND OBSTRUCTIONS

The CONTRACTOR shall anticipate all underground obstructions, such as water lines, gas lines, sewer lines, concrete, debris, and all other types of utility lines. No extra payment will be allowed for the removal, protection, replacement, repair or possible increased cost caused by underground obstruction. Any such lines or obstructions indicated on the Drawings show only the approximate location from the information available and must be verified in the field by the CONTRACTOR. The ENGINEER will endeavor to familiarize the CONTRACTOR with all underground utilities and obstructions, but this will not relieve the CONTRACTOR from full responsibility for anticipating all underground obstructions.

In accordance with C.R.S. Section 9-1.5-103 (1973), the CONTRACTOR shall not make or begin excavation without first notifying the owners, operators or association of owners and operators having underground facilities in the area of such excavation. Notice may be given in person, by telephone, or in writing and shall be given at least two business days prior to beginning work.

The CONTRACTOR shall protect the existing utilities in a manner as requested by the respective utility owners at no extra compensation. The CONTRACTOR, by their signature on this proposal and subsequently on the Agreement, agrees to hold City of Evans, the agencies thereof, and their officers and employees, harmless from any and all losses, damages or claims which may arise out of, or be connected with, construction performed where said utilities are located.

Should it be necessary to relocate utilities in the area of construction, the CITY, at its own expense, will coordinate these relocations with the utility owner and the CONTRACTOR.

#### 2.6.6 EMERGENCY WORK

In an emergency affecting the safety of life or of the work or of adjoining property, the CONTRACTOR is, without special instructions or authorization from the ENGINEER, hereby permitted to act at its discretion to prevent such threatening loss or injury. He shall also act, without appeal, if so authorized or instructed by the ENGINEER. Any compensation claimed by the CONTRACTOR as a result of emergency work, shall be determined by agreement or in accordance with Article 2.2.33.

#### 2.6.7 CLEANING UP

The CONTRACTOR shall remove, at their own expense, from the CITY's property and from all public and private property, all temporary structures, rubbish and waste materials resulting from their operations. This requirement shall not apply to property used for permanent disposal of rubbish or waste materials in accordance with permission of such disposal granted to the CONTRACTOR by the CITY thereof where such disposal is in accordance with local ordinances and is approved by the ENGINEER.

## ARTICLE 3.0

### SPECIAL CONDITIONS

#### INDEX

#### CONTENTS

3.1	GOVERNING DOCUMENTS .....	2
3.2	DESCRIPTION OF WORK .....	2
3.3	GENERAL .....	2
3.4	TECHNICAL SPECIFICATIONS .....	2
3.5	CONTRACT DRAWINGS AND VICINITY MAPS .....	3
3.6	PERMITS .....	3
3.7	SALES TAX .....	3
3.8	PROJECT TIME, SCHEDULE AND SEQUENCE .....	3
3.9	WORKING HOURS.....	3
3.10	PROJECT COORDINATION .....	4
3.11	CONSTRUCTION SURVEY .....	4
3.12	PROJECT WARRANTY .....	4
3.13	PRE-CONSTRUCTION MEETING .....	5
3.14	PROJECT MANAGER .....	5
3.15	JOB FOREMAN .....	5
3.16	MATERIALS, MANUFACTURER'S CERTIFICATES & RECOMMENDATIONS.....	5
3.17	LOAD RESTRICTIONS.....	6
3.18	CONSTRUCTION WATER .....	6
3.19	SANITATION FACILITIES .....	6
3.20	REMOVALS .....	7
3.21	EXISTING CONDITIONS.....	7
3.22	SAMPLES AND TESTING .....	7
3.23	CONTRACTORS AND SUBCONTRACTORS.....	8
3.24	MINOR ITEMS OF CONSTRUCTION .....	8
3.25	CONSTRUCTION TRAFFIC CONTROL .....	8
3.26	CLEANING DURING CONSTRUCTION.....	9
3.27	FINAL CLEANUP .....	9
3.28	SAFETY AND ACCIDENT PREVENTION.....	9
3.29	MEASUREMENT AND PAYMENT .....	9
3.30	LOCATION OF WORK.....	12

### **3.1 GOVERNING DOCUMENTS**

The governing documents for this Work are as follows:

- A. Contract Documents Articles 1.0 through 3.0
- B. The City of Evans, "Specifications for Street Design and Construction", dated August 2019.
- C. Colorado Department of Transportation, "Standard Specifications for Road and Bridge Construction", latest edition.

In the case of conflict, documents shall have the following priorities: (1) Contract Documents Article 3.0 – Special Conditions, (2) Contract Documents Article 2.0 – General Conditions, (3) Construction Drawings, (4) City of Evans "Specifications for Street Design and Construction", August 2019, and (5) Colorado Department of Transportation "Standard Specifications for Road and Bridge Construction", latest edition.

For all traffic control situations the "Manual on Uniform Traffic Control Devices", Current Edition, shall be used.

### **3.2 DESCRIPTION OF WORK**

The **Evans Gateway Sign and Landscaping at Evans Junction** project aims to improve the appearance of the corner at the intersection of 31st Street and Highway 85. The work will include installing a new entry sign and adding landscaping along the front area, based on the provided design.

### **3.3 GENERAL**

It is the intent of these Special Conditions to require a functionally complete project (or part thereof) to be constructed in accordance, and in conjunction with, all Contract Documents as defined within Article 1.0 – Contracting Procedures and Article 2.0 – General Conditions. Any work, materials, or equipment that may be reasonably inferred, as being required to produce the intended result will be provided whether or not specifically called for. When words, which have a well-known technical or trade meaning, are used to describe work, materials, or equipment, such words shall be interpreted in accordance with that meaning.

Use of these Special Conditions in conjunction with related Contract Documents to establish the total requirements of the project. The CONTRACTOR shall obtain all required documents and have them available during the execution of work. Exceptions, additions and/or modifications to the referenced documents are noted as follows:

### **3.4 TECHNICAL SPECIFICATIONS**

The technical specifications for the work are as referenced from the City of Evans "Specifications for Street Design and Construction", August 2019. The CONTRACTOR shall obtain this document and have it available during the execution of the work. Exceptions and/or modifications to the referenced document will be noted.

### **3.5 CONTRACT DRAWINGS AND VICINITY MAPS**

The contract drawings for this project include vicinity maps for each location where work will be performed to complete the project.

### **3.6 PERMITS**

Permits necessary for the prosecution of the work will be required for City projects, however, the CITY will waive the filing fee. CONTRACTOR must be a licensed contractor and have a City of Evans business license to work in the public right-of-way. All State of Colorado permits that may be required, depending on the project work being performed, are the responsibility of the CONTRACTOR. The Department of Public Works shall be notified before the planned construction is to commence and also before starting up after construction is delayed for any reason.

### **3.7 SALES TAX**

Sales Tax shall not be paid for materials purchased for use on this project.

### **3.8 PROJECT TIME, SCHEDULE AND SEQUENCE**

It is the intent of the CITY to award this project as soon as possible after receiving bids. The CONTRACTOR shall commence and complete work in accordance with the Agreement within Article 1.0 – Contracting Procedures.

At the pre-construction conference the CONTRACTOR shall submit and update a construction schedule which clearly outlines the work sequence. This schedule will be reviewed by the CITY, and when requested, the CONTRACTOR shall revise their work sequence to better suit job conditions. The CONTRACTOR shall comply with the requirements of Section 4 of the City of Evans “Specification for Street Design and Construction”.

It is the CONTRACTOR’s responsibility to complete this project within the prescribed time as stated in Article 1.0 – Contracting Procedures. A daily charge will be made against the Contractor for each calendar day that any work shall remain uncompleted after elapse of contract time. This daily charge will be deducted from any money due the Contractor. This deduction will not be considered as a penalty but as liquidated damages. The liquidated damages for this project will be as stated in Article 2.0 - General Conditions, Section 2.2.35.

### **3.9 WORKING HOURS**

The CONTRACTOR shall restrict working hours to between 7:00 A.M. and 7:00 P.M. on normal City of Evans business days unless otherwise approved by the City of Evans Project Manager. No work shall be performed on arterial or collector streets before 8:30 a.m. or after 3:30 p.m., unless otherwise approved by the City of Evans Project Manager. There shall be no work allowed on Saturdays, Sundays or Holidays unless approved, in writing, by the City Project Manager.

Costs incurred by the City to inspect work performed outside of these hours will be deducted from progress payments to the Contractor.

### **3.10 PROJECT COORDINATION**

The CONTRACTOR is responsible for contacting and coordinating with all project affected stakeholders. These affected stakeholders may include but are not limited to:

- A. Property Owners
- B. Utility Companies (listing of possible companies can be obtained from the City)
- C. Evans Police Department
- D. Evans Fire Protection District
- E. Weld County Sheriffs Department
- F. Weld County Ambulance
- G. Greeley-Evans School District 6
- H. Waste Management

The CONTRACTOR shall contact all appropriate utility companies to notify them of construction, to verify location of utilities in the construction area, and to coordinate utility company relocation, adjustment or installation work with the CONTRACTOR. The locations of utilities shown on the drawings are approximate. It is the responsibilities of the CONTRACTOR to field verify locations of utilities prior to initiating construction and to comply with the requirements of Section 4.03, Paragraphs J & K of the City of Evans "Specifications for Street Design and Construction". The City of Evans will not be responsible for any construction down time due to failure on the Contractors part to notify utility companies.

In addition, any street closures must be properly coordinated with any and all the affected stakeholders listed above. Proper traffic control measures per an approved Traffic Control Plan will be implemented – All anticipated closure times shall be approved by the CITY.

The CONTRACTOR is required to post on all properties adjacent to construction a notification pamphlet forty-eight (48) hours prior to commencement of work. The pamphlets shall only be delivered between the hours of 8:00 a.m. and 5:00 p.m. When delivering the pamphlets the Contractor shall make an effort to make personal contact with the resident or business to advise them what will be taking place on their street. If there is a delay due to weather, equipment and/or other causes, the Contractor shall post on all properties a re-notification pamphlet twenty-four (24) hours prior to commencement of work.

### **3.11 CONSTRUCTION SURVEY**

The CONTRACTOR shall provide the construction survey staking for the project in accordance with Section 4.03, Paragraph G of the "Specifications for Street Design and Construction". Construction survey and staking is considered incidental to the work, and no separate payment shall be made.

### **3.12 PROJECT WARRANTY**

The CONTRACTOR shall provide a two (2) year warranty for all construction beginning on the date of initial acceptance. All work that fails or deteriorates during the first or second year shall

be replaced under this warranty. There will be no additional cost to the CITY for material, equipment, labor and/or traffic control for warranty work. Warranty work shall be completed in accordance with these contract specifications within thirty (30) days of written notification by the CITY.

### **3.13 PRE-CONSTRUCTION MEETING**

The CONTRACTOR shall attend a pre-construction meeting after award of the contract. At the pre-construction meeting, the CONTRACTOR shall submit to the CITY:

- A. Pert or Gantt Chart of Construction Schedule
- B. Materials Supplier List
- C. Subcontractors List
- D. Concrete Mix Design
- E. Traffic Control Plan (approved by the City of Evans)
- F. Certificates of Insurance

### **3.14 PROJECT MANAGER**

The Project Manager designated at the pre-construction meeting by the Contractor will be responsible for the handling of all requests for information or complaints concerning the contract. A local telephone number will be established two weeks prior to commencement of construction. The Project Manager will respond to all requests within four hours. A log of all requests shall be kept and shall include name, telephone number, address, nature of request and response to such.

### **3.15 JOB FOREMAN**

The Job Foreman designated at the pre-construction meeting shall be on the work site during all construction. If the Foreman is unable to be on the job site, then a designee will be assigned with the authority to make all required decisions.

### **3.16 MATERIALS, MANUFACTURER'S CERTIFICATES & RECOMMENDATIONS**

Shop Drawings, samples and product data are required, by these specifications, on the following items before confirmation of orders:

- A. Hot Bituminous Pavement Mix Design (if needed)
- B. Concrete Mix Design
- C. Aggregate Base Course – Class 6 (if needed)

Certifications by the manufacturer that the material or equipment conforms to all applicable requirements shall be submitted. These certifications shall reference the standard specifications with which compliance is required.

### **3.17 LOAD RESTRICTIONS**

Truck load restrictions shall comply with Section 105.13, 105.14 and 105.15 of the Colorado Department of Transportation Standard Specifications for Road and Bridge Construction, current edition.

The Contractor shall keep fully informed of and comply with all Federal, State and local laws, ordinances, and regulations and all orders and decrees of bodies of tribunal having any jurisdiction or authority, which may affect the conduct of the work.

The Contractor will supply the City Project Manager with the axle load limits for the trucks he plans to use on this project.

### **3.18 CONSTRUCTION WATER**

Construction water shall consist of providing a water supply sufficient for the needs of the project and the hauling and applying of all water required. The CONTRACTOR SHALL NOT use water from local residences for construction purposes or to provide water to laborers.

The CONTRACTOR is encouraged to use water obtained from the Evans Ditch whenever possible. Contact the City of Evans Public Works Department to arrange for use of Evans Ditch water. Evans Ditch water may not be available at the time of construction.

The CONTRACTOR shall make arrangements for and provide all necessary water for his/her construction operation and domestic use at his/her own expense. The CONTRACTOR shall secure permission from the water utility and notify the ENGINEER and Fire Department/District before obtaining water from fire hydrants.

If the CONTRACTOR purchases water from a water utility at a fire hydrant on or near the project, all arrangements shall be made at his/her own expense and payment made direct to the water utility as agreed upon. The CONTRACTOR shall follow all rules and regulations of the respective district. Use only special hydrant-operating wrenches to open hydrants. Make certain that the hydrant valve is open "full" since cracking the valve causes damaged to the hydrant. If any hydrants are damaged, the CONTRACTOR will be held responsible and shall immediately notify the appropriate agencies so that all damages can be repaired as quickly as possible. Fire hydrants shall be completely accessible to the Fire Department/District at all times.

Construction Water for City projects will be made available from a hydrant or hydrant(s) local to the Site at no cost to the Contractor. However, the Contractor shall use a City-provided water meter for which a **\$1,200.00 deposit** will be required. Deposit and meter application shall be made at the Evans Community Center (City Hall) and the deposit will be returned to the Contractor when the meter is turned in at the end of Project.

### **3.19 SANITATION FACILITIES**

The CONTRACTOR shall meet all applicable requirements of OSHA, state and other governing agencies pertaining to sanitary facilities for workers. The CONTRACTOR shall provide chemical toilets of a suitable type and number and shall maintain the facilities in a sanitary condition at all times. The chemical toilets shall be of water-tight construction so that no contamination of the area can result from their use. Upon completion of the work, the sanitary facilities shall be removed and the area restored to its original condition.

### **3.20 REMOVALS**

The CONTRACTOR shall be responsible for locating sites and making arrangements for disposal of all materials removed from the sites. The CONTRACTOR's handling and disposition of excavation material shall be to a disposal site designated and/or approved by the ENGINEER. This includes concrete, asphalt, unsuitable or unstable subgrade material, and any other trash, rubbish or debris generated as a result of the construction. No trash, rubbish, or debris shall be allowed on the lawns of local residences by the CONTRACTOR's work force. No separate payment will be made for disposal of excavation material generated. This disposal shall be considered incidental to the construction and all costs thereof shall be included in various unit CONTRACT prices.

### **3.21 EXISTING CONDITIONS**

Prior to starting work on the project, the CONTRACTOR shall walk the project in the areas scheduled for work with the ENGINEER to determine the condition of fences, curbs, walls, drives, asphalt, lawns, sprinklers, and any other existing improvements (collectively surface improvements) that are to remain on both public and private property. The ENGINEER may record the existing condition of features using a video camera.

If in the opinion of the ENGINEER, there is sufficient operating space to perform the work in a reasonable manner without removing or destroying existing improvements, the CONTRACTOR shall perform the work without removing or destroying such improvements. In no event shall the CONTRACTOR remove trees, shrubs, vines, or other items without the prior approval of the ENGINEER. Intersections and driveways shall be closed for a minimum amount of time. The CONTRACTOR shall coordinate driveway closures with property owners with final approval by the City Project Manager.

The CONTRACTOR shall make every effort to prevent or limit damage to surface improvements. The CONTRACTOR is responsible for protecting or restoring all such surface facilities to their original or improved condition. Any existing improvements damaged by the CONTRACTOR shall be replaced by the CONTRACTOR at his/her own expense.

All materials shall be installed and/or applied, in kind, in accordance with applicable specifications.

### **3.22 SAMPLES AND TESTING**

All sampling and testing required by these specifications will be completed by an independent testing laboratory, hired by the CONTRACTOR and approved by the Owner. Tests are to be performed at the discretion of the ENGINEER for this project. Items to be tested are as shown:

- A. Concrete Sampling & Testing for Sidewalks, Bike Paths – (slump, air content, temperature, compressive strength, gradation)
- B. Concrete Sampling & Testing for Curb and Gutter – (slump, air content, temperature, compressive strength, gradation)
- C. Concrete Sampling & Testing for Structure Concrete – (slump, air content, temperature, compressive strength, gradation)

For all testing frequencies and/or minimum sampling values see Appendix B sheet vi of the "Specifications for Street Design and Construction", dated August 2019.

### **3.23 CONTRACTORS AND SUBCONTRACTORS**

All subcontractors are subject to approval by the CITY.

### **3.24 MINOR ITEMS OF CONSTRUCTION**

Minor items of construction which do not have a bid item provided will not be paid for separately. The costs of these items shall be subsidiary with other unit prices shown on the bid schedule.

### **3.25 CONSTRUCTION TRAFFIC CONTROL**

The CONTRACTOR shall submit a Traffic Control Plan and comply with the requirements of Section 4.03, Paragraph F of the "Specifications for Street Design and Construction". The CONTRACTOR shall not perform any construction work in the public right-of-way prior to receiving approval of the Traffic Control Plan from the CITY.

The approval of the Traffic Control Plan does not relieve the CONTRACTOR from responsibility to change or adjust traffic control devices if traffic or other conditions warrant. Any conditions or changes in project methods shall be submitted to the City Project Manager for review prior to making changes in the field.

The CONTRACTOR shall give proper advance notice to the CITY for approval. The portions applicable to city streets may be closed for short periods of time. The CONTRACTOR shall schedule work to minimize closures and must provide for local access. All anticipated closure times shall be approved by the CITY.

The CONTRACTOR shall appoint a Traffic Control Supervisor to this project. The Traffic Control Supervisor shall be certified as a Work Site Traffic Supervisor by the American Traffic Safety Services Association (ATSSA) or the Colorado Contractors Association (CCA).

All excavations or construction work that will be left open or exposed over night shall be protected with night time barricades and signing. The entire open excavation shall be properly fenced to protect both vehicular and pedestrian traffic.

All flaggers shall be properly trained according to State and Federal guidelines. A copy of each flaggers certification card will be submitted to the City Project Manager 48 hours to commencement of project.

The CONTRACTOR shall inspect all devices and operations a minimum of every 2 hours and repair and replace damaged or missing devices immediately during work hours. Work sites shall be inspected a minimum of every 24 hours during weekends or during periods when the Contractor is not actually performing work.

All work areas including, but not limited to, open cuts, trenches, ditches, manholes, and/or other hazards shall be completely surrounded by approved fencing and other appropriate controls to protect pedestrians and persons using bicycles, wheelchairs, and other vehicles. Temporary walkways must be provided and included on traffic control plans.

The CONTRACTOR agrees to hold harmless the City staff regarding accidents or claims

involving construction work and/or construction traffic control.

### **3.26 CLEANING DURING CONSTRUCTION**

During execution of work, the CONTRACTOR shall clean the sites, adjacent properties, and public access roadways on a daily basis at a minimum or as directed by the ENGINEER and shall dispose of waste materials, debris, and rubbish to assure that buildings, grounds, and public properties are maintained free from accumulations of waste materials and rubbish.

The CONTRACTOR shall wet down dry materials and rubbish to lay dust and prevent blowing dust.

The CONTRACTOR shall provide containers for collection and disposal of waste materials, debris, and rubbish.

The CONTRACTOR shall cover or wet loads of excavated material leaving the site to prevent blowing dust. The CONTRACTOR shall also clean the public access roadways to the site of any material falling from the haul trucks.

### **3.27 FINAL CLEANUP**

At the completion of the work and immediately prior to an initial inspection, the CONTRACTOR shall remove from the Construction Site all temporary structures and all materials, equipment, and appurtenances not required as part of, or appurtenant to, the completed work. The CONTRACTOR shall notify the CITY when final cleanup is ready for inspection.

The CONTRACTOR shall repair, patch, and touch-up marred surfaces to specified finish to match adjacent surfaces.

The CONTRACTOR shall broom clean paved surfaces and rake clean other surfaces of ground as necessary and as directed by the ENGINEER.

### **3.28 SAFETY AND ACCIDENT PREVENTION**

The Contractor shall take all reasonable precautions in the performance of the work under this contract to protect from all hazards to life and shall comply with all health, safety and fire protection regulations and requirements.

### **3.29 MEASUREMENT AND PAYMENT**

All materials will be measured and paid for in accordance to the Specifications. All material shall arrive at the job site with load or batch tickets indicating time loaded or batched, material type, material quantity, and date. A copy of the tickets shall be given to the ENGINEER the day the material arrives on site. Material delivered and placed without a load ticket will not be paid. The CITY will not pay for any material if the load ticket indicates that the vehicle and its load exceeded the legal weight limit for the vehicle type.

All work performed and all materials furnished shall conform to the requirements, including tolerances, provided herein. Materials not in conformance with these specifications, but allowed to remain in place by the ENGINEER may be subject to applicable price reductions as specified in Section 105.03 of the Colorado State Department of Transportation "Standard Specifications for Road and Bridge Construction", current edition.

The CONTRACTOR is responsible for providing a product that is in conformance with the specification provided herein. Suitability of the finished product will be determined by the ENGINEER. A finished product that is not found suitable by the ENGINEER, may be subject to:

- A. Disapproval and subsequent removal and replacement of the material/product at the CONTRACTOR's expense.
- B. A reduction in pay as outlined with formulas in the Colorado Department of Transportation "Standard Specifications for Road and Bridge Construction", current edition. The Colorado Department of Transportation Standard Specifications is strictly used for determining the actual reduction of pay for unsuitable material/product and is not used to determine suitability of a final product. The ENGINEER will determine suitability.
- C. The ENGINEER allows questionable product/material to remain in place with the CONTRACTOR providing some type of remedial action to make the product/material suitable. Type of remedial action to be determined by ENGINEER and paid for by CONTRACTOR.
- D. The addition of an extended warranty for questionable materials/products to allow further review to determine suitability and any further action by CONTRACTOR at the end of the warranty period.

The measurement and payment for this project shall be as written specifically for this project and included in this Article of the Contract Document.

The work performed under this Agreement shall be paid for on a unit price basis at the rate for the respective items on the Bid Schedule. The quantities provided on the Bid Schedule are only estimates of the actual quantities of the work to be performed, and are only included for purposes of making the award. The CITY reserves the right to alter and/or eliminate any item of work. Modifications, if any, will be made by Change Order.

Unless otherwise provided for specifically in this section, all lump sum bid items will be paid for upon completion of all work associated with the lump sum bid item.

Payment shall be made only for those items included in the PROPOSAL. All other costs incurred shall comply with the provisions of these Specifications and shall be included in the unit price bid for the associated items in the PROPOSAL. Except as may be otherwise stipulated, no material, labor, or equipment will be furnished by the CITY. The quantity of work which will be considered for payment is the actual number of units completed in accordance with all relative specifications.

- 1. Measurements:
  - a. No measurement for payment shall be made for any of the work, materials and equipment required for mobilization. A lump sum payment will be made.

- b. The quantities of work to be paid will be measured as identified within Article 1.0 – Bid Schedule to perform work, including but not limited to, the furnishing and installation of all components and accessories, in accordance with the Contract Documents. No payment for items outside of the dimensions shown on the Drawings or field markings, unless directed and approved by the ENGINEER, will be included in the amount computed for payment.
- c. No separate measurement shall be made for fittings and accessories necessary to install bid item.
- d. No measurement for payment shall be made for removal or replacement of materials and/or existing features damaged by the CONTRACTOR in his operation.

2. Payments:

- a. Mobilization & demobilization lump sum bid prices shall include all the CONTRACTOR's cost whatsoever the nature required for mobilization of personnel, equipment, construction trailers, or supplies at the project site in preparation for work on the project, and demobilization, location and protection of utilities. This item shall also include the establishment of all necessary facilities, on-site restrooms, and all other costs incurred or labor and operations that must be performed prior to beginning the other items under Contract. Also, to be included shall be all costs whatsoever to obtain any and all required permits, taxes, licenses, fees, and bonds necessary as required by the CITY, water and sanitary districts, and other municipal governments to perform the Work. This item may also include the cost of required bonds, insurance, preparation of the Project schedule and required shop drawings, and clean-up of the site.
- b. Mobilization & demobilization payment will be made as the work progresses. Fifty percent (50%) of the lump sum bid price will be paid at the time of the first monthly progress payment. An additional thirty percent (30%) will be paid when one-half the original contract is earned separately on each of the bid schedules. The remaining twenty percent (20%) will be paid upon final acceptance of the project.
- c. Payment for the Bid Item other than mobilization & demobilization shall include full compensation for, but is not limited to, all materials, labor, supplies, transportation, disposal, equipment required to complete the work in accordance with the Contract Documents.
- d. No separate payment shall be made for fittings and accessories necessary to install bid item.
- e. CONTRACTOR will not be reimbursed for the retesting of any materials that fail, or due to inclement weather, or for any other reason. All samples required for testing will be provided by the CONTRACTOR and at no cost to the OWNER.
- f. Excess excavation shall be disposed of off-site and shall not be paid for separately.
- g. All samples required for testing will be provided by the CONTRACTOR and at no cost to the OWNER.

### **3.30 LOCATION OF WORK**

It is the intent of the attached vicinity maps to give the general location of the work to be performed under this contract. The final designation of locations will be verified after the contract has been awarded. The City reserves the right to alter quantities (both increase and decrease) from those shown on the plan and bidder's documents. Such alterations or quantities will not change the unit price of the accepted contract, except that if quantities are increased or decreased by more than twenty-five percent (25%) of the total contract, then a mutually agreeable adjustment may be made.

## ARTICLE 4.0

### MEASUREMENT & PAYMENT

#### INDEX

##### CONTENTS

4.1	DESCRIPTION.....	2
4.1.1	BID PRICE .....	2
4.1.2	ESTIMATED QUANTITIES .....	2
4.1.3	PAYMENT .....	2
4.1.4	PAY QUANTITIES.....	3
4.2	GENERAL .....	3
4.2.1	MOBILIZATION & DEMOBILIZATION .....	3
4.2.2	EROSION AND SEDIMENT CONTROL .....	4
4.2.3	CLEANUP AND RESTORATION.....	4
4.3	LANDSCAPE AND IRRIGATION.....	4
4.3.1	TOPSOIL & SOIL AMENDMENTS.....	5
4.3.2	BOULDERS.....	5
4.3.3	TREES, SHRUBS AND GROUND COVER .....	5
4.3.4	MULCH.....	6
4.3.5	MISCELLANEOUS LANDSCAPE .....	6
4.3.6	IRRIGATION COMPONENTS .....	7

## **4.1 DESCRIPTION**

This Section covers methods of measurements and payment for items of Work.

Owner will not pay for defective work and will not pay for repair or additional work required to bring the projects to a point of acceptance.

### **4.1.1 BID PRICE**

The Total Bid Price covers all Work required by the Contract Documents.

All work not specifically set forth as a pay item in the Bid Form shall be considered a subsidiary obligation of Contractor and all costs in connection therewith shall be included in the prices bid for the various items of Work.

Unit prices shall include all costs in connection with the proper successful completion of the Work, including furnishing all materials, equipment and tools; and performing all labor and supervision to fully complete the Work.

Unit prices shall govern over extensions of sums.

Unit prices shall not be subject to renegotiation.

### **4.1.2 ESTIMATED QUANTITIES**

All quantities stipulated in the Bid Form at unit prices are approximate and are to be used only as a basis for estimating the probable cost of the Work and for the purpose of comparing the bids submitted for the Work. The basis of Payment will be the actual quantity of material furnished and Work done.

Contractor agrees that he will make no claim for damages, anticipated profits, or otherwise on account of any difference between the amount of Work actually performed and materials actually furnished and the estimated amount.

Owner reserves the right to decrease, increase, or delete units of work.

### **4.1.3 PAYMENT**

Partial payment under the Contract shall be made at the request of the CONTRACTOR once each month, based upon partial estimates to be furnished by the CONTRACTOR and approved by the ENGINEER or inspector. In making such partial payment, there shall be retained five percent (5%) of the estimated amounts until final completion and acceptance of all work covered by the Contract; provided, however, that the ENGINEER, at any time after fifty percent (50%) of the work has been completed, finds that satisfactory progress is being made, shall recommend that the remaining partial payment be paid in full.

In preparing estimates for partial payments, the material delivered on the site and preparatory work done may be taken into consideration.

Payments for work under subcontracts of the CONTRACTOR shall be subject to the above

conditions applying to the contract after the work under a subcontract has been fifty percent (50%) completed. In preparing estimates for partial payments, the material delivered on the site and preparatory work done may be taken into consideration.

Should the CONTRACTOR fail to proceed properly and in accordance with the Guarantee, the CITY may have such work performed at the expense of the CONTRACTOR.

#### 4.1.4 PAY QUANTITIES

The CONTRACTOR shall be paid on a unit price basis as indicated by the proposal for the actual quantities installed.

### 4.2 GENERAL

#### 4.2.1 MOBILIZATION & DEMOBILIZATION

No measurement for Payment will be made for any of the work, materials, and equipment required for mobilization and demobilization. The lump sum bid price shall include all of the CONTRACTOR's costs of whatsoever nature including site management and full-time supervision, labor, material, and any incidental work and equipment necessary for mobilization and demobilization of personnel, equipment and supplies at the project site.

This item includes installation of temporary fencing around project work areas, and any other fencing/security items as deemed necessary by the CONTRACTOR. This item shall also include the establishment of other necessary facilities not specifically defined as a separate pay item, and all other costs incurred of labor and operations which must be performed prior to beginning the other items under this Contract. This item also includes obtaining permits and CONTRACTOR testing. This item may also include provision of required bonds, insurance and preparation of the project schedule. The removal of the CONTRACTOR's equipment, supplies, excess materials, and cleanup of the site are also included in this item.

Payment will be made as the work progresses in accordance with bid documents.

<u>Pay Item</u>	<u>Pay Unit</u>
Mobilization and Insurance (Landscape & Irrigation)	1 LS

#### 4.2.2 EROSION AND SEDIMENT CONTROL

No measurement for Payment will be made for any of the work, materials, and equipment required for erosion and sediment control. The lump sum bid price shall include all of the CONTRACTOR's costs of whatsoever nature including site management and full-time supervision, labor, material, and any incidental work and equipment necessary for erosion and sediment control at the project site.

These items shall also include materials and installation of rock socks, silt fence, inlet protection, regular street cleaning and other items as called for on the plans and specifications.

Payment will be made as the work progresses.

<u>Pay Item</u>	<u>Pay Unit</u>
Stabilization Staging Area	1 LS
Street Sweeping	40 HR
Vehicle Tracking Control	1 EA
Inlet Protection	4 EA

#### 4.2.3 Cleanup and Restoration

No measurement for Payment will be made for any of the work, materials, and equipment required for cleanup and restoration. This lump sum price shall include all costs to perform all work necessary to remove, restore, install and replace all above grade improvements including but not limited to signs, fences, gates, and all other items not covered elsewhere in the bid form and any other miscellaneous items and work shown or reasonably implied on the Drawings and in the Specifications for this work, and elsewhere in the Contract Documents.

Payment will be made based on the percentage of all work completed at the time of each Progress Payment.

<u>Pay Item</u>	<u>Pay Unit</u>
Restoration of Staging Area	1 LS

### 4.3 LANDSCAPE AND IRRIGATION

#### 4.3.1 TOPSOIL AND SOIL AMENDMENTS

The measurement for payment for each pay item will be on a unit price basis. The unit price includes but is not limited to furnishing and placement of materials and labor required to construct the pay item complete and in place in accordance with the Drawings and Specifications.

The work includes but is not limited to materials and equipment required for excavation,

transportation and placement of topsoil and soil amendment material within the Limits of Construction as designated in the Landscape Drawings.

Payment will be made based on the actual quantity installed.

<u>Pay Item</u>	<u>Pay Unit</u>
TOPSOIL	100 CY
SOIL AMENDMENT	150 CY

#### 4.3.2 BOULDERS

The measurement for payment for each pay item will be on a unit price basis. The unit price includes but is not limited to furnishing and placement of materials and labor required to construct the pay item complete and in place in accordance with the Drawings and Specifications.

The work includes but is not limited to materials and equipment required for excavation, transportation and placement of boulders within the Limits of Construction as designated in the Landscape Drawings.

Payment will be made based on the actual quantity installed.

<u>Pay Item</u>	<u>Pay Unit</u>
SILOAM BOULDERS (APPRX. 3'X3')	60 EA

#### 4.3.3 TREE, SHRUBS AND GROUND COVER

The measurement for payment for each pay item will be on a unit price basis. The unit price includes but is not limited to furnishing and placement of materials and labor required to construct the pay item complete and in place in accordance with the Drawings and Specifications.

The work includes but is not limited to materials and equipment required for transportation, excavation for, and installation of trees, shrubs and groundcover within the Limits of Construction as designated in the Landscape Drawings and in the Specifications.

Payment will be made based on the actual quantity installed.

<u>Pay Item</u>	<u>Pay Unit</u>
EVERGREEN TREES	6 EA
DECIDUOUS TREES	22 EA
1 GALLON SHRUBS/ PERENNIALS	127 EA
5 GALLON SHRUBS	137 EA
SOD	4,200 SF
SEEDING (ALL MIX TYPES)	35,300 SF

#### 4.3.4 MULCH

The measurement for payment for each pay item will be on a unit price basis. The unit price

includes but is not limited to furnishing and placement of materials and labor required to construct the pay item complete and in place in accordance with the Drawings and Specifications.

The work includes but is not limited to materials and equipment required for transportation and placement of Mulch within the Limits of Construction as designated in the Landscape Drawings.

Payment will be made based on the actual quantity installed.

<u>Pay Item</u>	<u>Pay Unit</u>
ROCK MULCH (1"-2" CHIP)	55 CY
ROCK COBBLE (3"-6")	230 CY
WEED BARRIER FABRIC AND STAPLES	18,000 SF

#### 4.3.5 MISCELLANEOUS LANDSCAPE

The measurement for payment for each pay item will be on a unit price basis. The unit price includes but is not limited to furnishing and placement of materials and labor required to construct the pay item complete and in place in accordance with the Drawings and Specifications.

The work includes but is not limited to materials and equipment required for, transportation excavation, installation of the following landscape features within the Limits of Construction as designated in the Landscape Drawings.

Payment will be made based on the actual quantity installed.

<u>Pay Item</u>	<u>Pay Unit</u>
EDGING	1,500 LF
FENCING	315 LF

#### 4.3.5 MONUMENT SIGN

The measurement for payment for each pay item will be on a unit price basis. The unit price includes but is not limited to furnishing and placement of materials and labor required to construct the pay item complete and in place in accordance with the Drawings and Specifications.

The work includes but is not limited to materials and equipment required for, transportation excavation, installation of the following landscape features within the Limits of Construction as designated in the Landscape Drawings.

Payment will be made based on the actual quantity installed.

<u>Pay Item</u>	<u>Pay Unit</u>
GABION WALL	100 SF
CORTEN PANELS	2 EA
SIGNAGE (LETTERS AND LOGOS)	1 EA
SIGN LIGHTING AND ELECTRICAL	1 LS

#### 4.3.6 IRRIGATION COMPONENTS

The measurement for payment for each pay item will be on a unit price basis. The unit price includes but is not limited to furnishing and placement of materials and labor required to construct the pay item complete and in place in accordance with the Drawings and Specifications.

The work includes but is not limited to materials and equipment required for, transportation of materials, excavation, installation of the following landscape irrigation features within the Limits of Construction as designated in the Landscape Drawings.

Payment will be made based on the actual quantity installed.

<u>Pay Item</u>	<u>Pay Unit</u>
CONTROLLER WITH PEDESTAL (INCLUDES POWER)	1 EA
METER CONNECTION	1 EA
BACKFLOW PREVENTOR	1 EA
MASTER VALVE	1 EA
RAIN/FREEZE SENSOR	1 EA
FLOW SENSOR	1 EA
MAIN LINE	485 LF
SPRAY AREA (INCLUDES ALL LATERALS, FITTING HEADS AND VALVES)	24,000 SF
DRIP AREA (INCLUDES ALL LATERAL, FITTINGS, HEADS AND VALVES)	9,500 SF
TREE RINGS	28 EA
SLEEVING	75 LF

**ARTICLE 5.0**

**Vicinity Map and Plan Set**

**INDEX**


PROJECT SITE VICINITY MAP ..... 1 Sheet

100% CD-BID SET ..... 12 Sheets

# GATEWAY SIGN AND LANDSCAPING AT EVANS JUNCTION

SOUTHWEST CORNER OF 31ST AVE AND HIGHWAY 85  
CITY OF EVANS, COUNTY OF WELD, STATE OF COLORADO


## PREPARED FOR:



1100 37TH ST  
EVANS COLORADO 80620

## CONTACTS

OWNER	CITY OF EVANS 1100 37TH STREET EVANS, CO 80620 970-475-1170
LANDSCAPE ARCHITECT	JORIE CREEL SANBELL 425 WEST MULBERRY STREET, STE. 201 FORT COLLINS, CO 80521 970-773-7732
CIVIL ENGINEER	JOHN E. TUFTE, PE SANBELL 425 WEST MULBERRY STREET, STE. 201 FORT COLLINS, CO 80521 970-893-2106
SURVEYOR	PETE PAULUS, PLS SANBELL 425 WEST MULBERRY STREET, STE. 201 FORT COLLINS, CO 80521 970-549-0630
WATER & STORMWATER	CITY OF EVANS PUBLIC WORKS 970-475-1182
ELECTRIC (XCEL)	XCEL ENERGY 970-395-1207
GAS	ATMOS ENERGY 970-534-0288
TELECOM.	CENTURYLINK / LUMEN 303-726-2998
CABLE	COMCAST 970-336-6013
FIBER OPTIC	ALLO FIBER 719-221-4374
FIBER OPTIC	VERO NETWORKS 901-508-2946



## VICINITY MAP

NOT TO SCALE

### PROJECT SPECIFIC NOTES:

-EXISTING UNDERGROUND INSTALLATIONS & PRIVATE UTILITIES SHOWN ARE INDICATED ACCORDING TO THE BEST INFORMATION AVAILABLE TO THE ENGINEER. THE ENGINEER DOES NOT GUARANTEE THE ACCURACY OF SUCH INFORMATION. SERVICE LINES (WATER, POWER, GAS, STORM, SEWER, TELEPHONE & TELEVISION) MAY NOT BE STRAIGHT LINES OR AS INDICATED ON THE PLANS. STATE LAW REQUIRES CONTRACTOR TO CALL ALL UTILITY COMPANIES BEFORE EXCAVATION FOR EXACT LOCATIONS.

-UNLESS OTHERWISE SPECIFIED, ALL CONSTRUCTION LAYOUT AND STAKING SHALL BE PERFORMED UNDER THE RESPONSIBLE CHARGE OF A LAND SURVEYOR LICENSED IN THE STATE WHERE THE PROJECT IS LOCATED AND BY A PARTY CHIEF OR ENGINEERING TECHNICIAN EXPERIENCED IN CONSTRUCTION LAYOUT AND STAKING TECHNIQUES AS ARE REQUIRED BY THE SPECIFIC TYPE OF WORK BEING PERFORMED.

FIELD SURVEY FOR THIS PROJECT WAS COMPLETED 06/21/2024 BY SANBELL.  
DRONE IMAGERY AND SURFACE WERE FLOWN ON 05/24/2024 BY SANBELL.  
UTILITY LOCATES WERE COMPLETED BY KINETIC INDUSTRY/PROVAC ON 04/23/2024.  
CORE DRILLING FOR FOUNDATION AND SLAB THICKNESS WERE COMPLETED BY KINETIC INDUSTRY/PROVAC ON 07/02/2024.  
GEOTECHNICAL ENGINEERING WAS COMPLETED BY CTL ON 06/17/2024.

Sheet Number	Sheet Title	PAGE NUMBER
L1.0	LANDSCAPE COVER	1
L1.1	LANDSCAPE LEGEND AND NOTES	2
L1.2	OVERALL LANDSCAPE PLAN	3
L1.3	LANDSCAPE PLAN- NORTH	4
L1.4	LANDSCAPE PLAN- SOUTH	5
L1.5	LANDSCAPE PLAN- SIGN	6
L2.1	LANDSCAPE DETAILS	7
L2.2	LANDSCAPE DETAILS	8
L2.3	LANDSCAPE DETAILS	9
L3.1	IRRIGATION SCHEDULE & NOTES	10
L3.2	IRRIGATION PLAN-NORTH	11
L3.3	IRRIGATION PLAN-SOUTH	12
L4.1	IRRIGATION DETAILS	13

## PROJECT CONTROL

ALL DISTANCES SHOWN WERE MEASURED IN US SURVEY FEET.

### BASIS OF BEARINGS AND LINEAL UNIT DEFINITION

THE BEARINGS IN THIS SURVEY ARE BASED ON NAD83 (2011) COLORADO NORTH STATE PLANE COORDINATES. THE GRID DISTANCES WERE CONVERTED TO GROUND BY APPLYING A COMBINED SCALE FACTOR OF 1.0002600000 AT (0,0).

THE NORTH LINE OF THE SOUTHWEST QUARTER OF SECTION 20, TOWNSHIP 5 NORTH, RANGE 65 WEST BEARS NORTH 89°42'08" EAST FROM THE WEST QUARTER CORNER OF SAID SECTION 20, AS MARKED BY A 3/4 INCH DIAMETER REBAR WITH A 3-1/4 INCH DIAMETER ALUMINUM CAP, LS38348, DATED 2015, TO THE CENTER QUARTER CORNER OF SAID SECTION 20, MONUMENTED BY TWO REFERENCE CORNERS, 3-1/4" ALUMINUM CAPS, LS22098, 88.21 FEET SOUTHWEST OF THE CORNER LOCATION AND 77.59 FEET NORTHEAST OF THE CORNER LOCATION, WITH ALL BEARINGS HEREIN RELATIVE THERETO.

## VERTICAL CONTROL

ALL ELEVATIONS IN THIS SURVEY ARE BASED ON THE NAVD88 ADJUSTED VERTICAL DATUM.

## VERTICAL BENCHMARKS

CITY OF EVANS NO. 8 ELEVATION = 4644.51  
DESCRIPTION- 2 INCH ALUMINUM CAP IN SOUTHWEST CORNER OF OUTLET STRUCTURE, SOUTHWEST CORNER OF 37TH STREET AND RIVERSIDE PARKWAY, 36 FEET SOUTH OF THE BACK OF CURB OF 37TH STREET, 65.4 FEET WEST OF THE BACK OF WALK OF RIVERSIDE PARKWAY.

CITY OF EVANS NO. 14 ELEVATION = 4646.60  
DESCRIPTION- 2 INCH ALUMINUM CAP IN SET IN SOUTH END OF HEADWALL NEAR THE NORTHWEST CORNER OF THE INTERSECTION OF 1ST AVENUE AND 31ST STREET, ON THE WEST SIDE OF 1ST AVENUE, 29 FEET WEST OF THE WEST EDGE OF ASPHALT OF 1ST AVENUE, 36.8 FEET NORTH OF THE NORTH EDGE OF ASPHALT OF 31ST STREET.

FILE:	24058_LS_COVER.DWG
PROJECT NO:	24058
CAD:	TH/JC
QUALITY ASSURANCE:	KP/JET

DRAWING HISTORY	
DATE	DESCRIPTION
02/06/2025	100% CD
09/11/2025	100% CD- BID SET
-	-
-	-
-	-
-	-
-	-
-	-
-	-



GENERAL NOTES

1. THE CONTRACTOR SHALL OBTAIN, AT THEIR OWN EXPENSE, APPLICABLE LICENSES, STANDARDS, PERMITS, ETC. WHICH ARE NECESSARY TO PERFORM THE WORK.
2. THE CONTRACTOR SHALL LOCATE, CLEARLY MARK AND MAINTAIN EXISTING UTILITIES ON THE SITE PRIOR TO WORK START UP. CALL FOR UTILITY LOCATES PRIOR TO COMMENCING WORK.
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL UTILITIES AND REPAIR OF UTILITIES IF DAMAGED. REPAIR SHALL BE DONE AT NO ADDITIONAL COST TO THE OWNER
4. ALL DIMENSIONS SHALL BE FIELD VERIFIED BY CONTRACTOR PRIOR TO CONSTRUCTION. ANY DEVIATION FROM THESE PLANS MUST BE APPROVED BY OWNER OR LANDSCAPE ARCHITECT PRIOR TO CONSTRUCTION.
5. LIMIT OF WORK IS AS INDICATED ON THE PLANS.
6. COORDINATE SITE ACCESS, STAGING, STORAGE AND CLEANOUT AREAS WITH OWNER'S REPRESENTATIVE.

PLANTING NOTES

1. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL PLANT QUANTITIES. GRAPHIC QUANTITIES TAKE PRECEDENCE OVER WRITTEN QUANTITIES.
2. ALL LANDSCAPE AREAS SHALL RECEIVE SOIL PREPARATION PER CITY OF EVANS LAWN AND GRASS SPECIFICATION SECTION 02930.
3. ALL EXISTING GRASS STAND AREAS DISTURBED BY CONSTRUCTION OPERATIONS SHALL BE SOIL PREPARED AND SEEDED BY THE CONTRACTOR.
4. ALL LANDSCAPE MATERIALS SHALL BE INSTALLED ACCORDING TO SOUND HORTICULTURAL PRACTICES AND AMERICAN NURSERY STANDARDS IN A MANNER DESIGNED TO ENCOURAGE QUICK ESTABLISHMENT AND HEALTHY GROWTH.
5. REPAIR DISTURBED AREAS BENEATH SHRUBS BY HAND.
6. REPAIR AND RESEED STAGING AREA.
7. CONTRACTOR SHALL COORDINATE IRRIGATION AND PLANTING WORK SUCH THAT INSTALLED IRRIGATION EQUIPMENT SHALL NOT CAUSE ADJUSTMENT OF PLANTING LOCATIONS CONTRARY TO THE PLANS. IF IRRIGATION EQUIPMENT IS INSTALLED IN LOCATIONS OBSTRUCTING THE INTENDED LOCATIONS OF THE PLANTINGS, NOTIFY THE LANDSCAPE ARCHITECT FOR CLARIFICATION.
8. THE CONTRACTOR SHALL WARRANTY ALL CONTRACTED WORK AND MATERIALS FOR A PERIOD OF ONE YEAR AFTER SUBSTANTIAL COMPLETION HAS BEEN ISSUED BY THE OWNER'S REPRESENTATIVE FOR THE ENTIRE PROJECT UNLESS OTHERWISE SPECIFIED IN THE CONTRACT DOCUMENTS OR SPECIFICATIONS.
9. AREAS TO BE SEEDED OR SODDED TO BE AMENDED WITH 4 CUBIC YARDS OF COMPOST PER 1,000 SQUARE FEET.
10. ALL MANHOLE COVERS SHALL BE AT OR ABOVE GRADE.
11. ALL ROCK AND SHRUB BEDS SHALL HAVE WEED BARRIER FABRIC.

CITY OF EVANS LANDSCAPE NOTES

ALL AREAS DISTURBED BY CONSTRUCTION ACTIVITIES THAT WILL REMAIN AS OUTLOTS, OPEN SPACE, DETENTION PONDS, FOREBAYS, OR TRAILS SHALL RECEIVE 4 INCHES OF TOP SOIL AND SHALL BE SEEDED.SOIL PREPARATION, FERTILIZER, COMPOST, SEEDING, AND MULCHING WILL BE REQUIRED.

ALL PLANTINGS REQUIRED SHALL UTILIZE THE CITY OF EVANS PARKS AND RECREATION APPROVED LANDSCAPING PLANTING LIST.

























ALL SEEDING SHALL UTILIZE THE CITY OF EVANS IRRIGATION DESIGN GUIDELINES AND LAWN AND GRASS SPECIFICATIONS SECTION 02930.

GRASS SEED SHALL BE PLANTED WITH A GRASS SEED DRILL (NOT A GRAIN DRILL) AT A DEPTH OF ½" TO ¾". BROADCAST SEEDING OF GRASS SEED IS NOT ACCEPTABLE. STRAW MULCH SHALL BE SPREAD AND CRIMPED INTO THE SOIL AT A RATE OF 4,000 LBS/ACRE. HYDROSEEDING AND HYDROMULCHING IS ACCEPTABLE IN LIEU OF DRILL SEEDING AND CRIMPING OF MULCH STRAW. ONLY IN AREAS THAT ARE INACCESSABLE TO LANDSCAPING EQUIPMENT, AND MUST BE APPROVED BY THE CITY OF EVANS PRIOR TO USE.


ALL PLANTINGS REQUIRED BY THE PLANNING DIVISION APPROVED LANDSCAPING PLAN SHALL UTILIZE THE CITY OF EVANS PARKS AND RECREATION APPROVED LANDSCAPING PLANTING LIST.

ALL SEEDING REQUIRED BY EITHER THE CITY OF EVANS ENGINEERING DIVISION, OR PLANNING DIVISION SHALL UTILIZE THE CITY OF EVANS PARKS AND RECREATION IRRIGATION DESIGN GUIDELINES.

LEGEND

SYMBOL	CODE	BOTANICAL / COMMON NAME	SIZE	QTY
TREES				
	CI	CRATAEGUS CRUS-GALLI INERMIS / THORNLESS COCKSPUR HAWTHORN	2" CAL	2
	GT	GLEDITSIA TRIACANTHOS F. INERMIS / THORNLESS HONEY LOCUST	2" CAL.	9
	PN	PINUS NIGRA / AUSTRIAN PINE	B & B 6' MIN. HT.	6
	QM	QUERCUS MACROCARPA / BURR OAK	2" CAL.	11
SHRUBS				
	BC	BERBERIS THUNBERGII 'CRIMSON PYGMY' / CRIMSON PYGMY JAPANESE BARBERRY	5 GAL.	17
	DF	DASIPHORA FRUTICOSA 'GOLD DROP' / GOLD DROP BUSH CINQUEFOIL	5 GAL.	9
	EF	EUONYMUS FORTUNEI / WINTERCREEPER	5 GAL.	39
	FC	FORSYTHIA X 'COURTASOL' / GOLD TIDE® FORSYTHIA	5 GAL.	28
	PN2	PICEA ABIES 'NIDIFORMIS' / BIRD'S NEST NORWAY SPRUCE	5 GAL	21
	RA	RHUS AROMATICA / FRAGRANT SUMAC	5 GAL.	23
GRASSES				
	CA	CALAMAGROSTIS X ACUTIFLORA / FEATHER REED GRASS	1 GAL.	51
	FE	FESTUCA GLAUCA 'ELIJAH BLUE' / ELIJAH BLUE FESCUE	1 GAL	16
	PH	PENNISETUM ALOPECUROIDES 'HADELN' / HAMELN FOUNTAIN GRASS	1 GAL.	10
PERENNIALS				
	PB	PHLOX SUBULATA 'BLUE' / BLUE CREEPING PHLOX	1 GAL.	10
	PW	PHLOX SUBULATA 'RED WINGS' / RED WINGS CREEPING PHLOX	1 GAL.	9
	RH	RUDBECKIA HIRTA / BLACK-EYED SUSAN	1 GAL.	30
	VC	VINCA MINOR 'BOWLES' / BOWLES PERIWINKLE	1 GAL.	11
SYMBOL	CODE	BOTANICAL / COMMON NAME	CONT	QTY
GROUND COVERS				
	AE7	DETENTION POND SEED MIX WESTERN WHEATGRASS 90% ALKALIGRASS 10% APPLY 30 LBS/ACRE BY SEED DRILLER	SQFT	10,420 SF
	AE	GRASS SOD BLUEGRASS FECSUE BLEND ROADSIDE LOW GROW SEED MIX	SQFT	4,179 SF
	AE6	SEED MIX- BUFFALOGRASS 60% BLUE GRAMMA 40% APPLY AT 22 LBS/ACRE	SQFT	14,837 SF
	AE2	ROCK COBBLE 3-6" RIVER COBBLE, 6" DEPTH	SQFT	12,255 SF
	AE5	ROCK MULCH 1-2" ROCK CHIP, 3" DEPTH	SQFT	5,413 SF
	AE4	SHORT GRASS NATIVE SEED MIX SEED MIX- SAND DROPSEED 10% BLUE GRAMA 27% LITTLE BLUESTEM 26% SIDEOATS GRAMA 27% SAND LOVEGRASS 10% APPLY AT 11 LBS/ACRE BY SEED DRILLER	SQFT	5,359 SF
	AE3	TALL NATIVE GRASS SEED MIX SEED MIX- PRAIRIE SANDREED 30% SAND BLUESTEM 30% YELLOW INDIAN GRASS 30% SWITCHGRASS 10% APPLY AT 21 LBS/ACRE BY SEED DRILLER	SQFT	8,854 SF

100% CD-BID SET



**sanbell**  
Intelligent Infrastructure. Enduring Communities.

DRAWING HISTORY

FILE: 24058\_LS\_PROD.DWG

PROJECT NO: 24058

CAD: TH/JC

QUALITY ASSURANCE: KP/JET

DRAWING HISTORY

DATE DESCRIPTION

02/06/2025 100% CD

09/11/2025 100% CD-BID SET

-

-

-

-

-


GATEWAY SIGN AND LANDSCAPING AT EVANS JUNCTION

SOUTHWEST CORNER OF 31ST AVE AND HIGHWAY 85

EVANS COLORADO


LANDSCAPE LEGEND AND NOTES

11.1






P:\24058\_Evans\_Junction\_Retail\CADD\_CDR\PRODUCTION\_DWG\24058\_LS\_PROD.dwg, L1.3 SIGN LANDSCAPE PLAN, 9/11/2025 2:21:23 PM, sheet, 1 of 1




P:\24058\_Evans\_Colorado\_Retail\CADD\CADDPRODUCTION\_DWG\24058\_LS\_PROD.mxd, L1:317FORM LANDSCAPE PLAN, 9/11/2025 2:21:32 PM, Sheet: 11



LANDSCAPE PLAN- SOUTH



SCALE SHOWN IS ACCURATE WHEN  
PRINTED ON 22X34 SHEET WITH 1:1  
PLOT SCALE. DOUBLE SCALE ON  
11X17 SHEET WITH 1:2 PLOT SCALE.



100% CD-BID SET

**GATEWAY SIGN AND LANDSCAPING AT EVANS JUNCTION**  
SOUTHWEST CORNER OF 31ST AVE AND HIGHWAY 85  
  
EVANS COLORADO  
LANDSCAPE PLAN- SOUTH


DRAWING HISTORY	
DATE	DESCRIPTION
02/06/2025	100% CD
09/11/2025	100% CD- BID SET
-	-
-	-
-	-
-	-
-	-
-	-
FILE:	24058_LS_PROD.DWG
PROJECT NO:	24058
CAD:	TH/JC
QUALITY ASSURANCE:	KP/JET




P:\24058\_Evans\_Colorado\_Retail\CADD\_CD\PRODUCTION\_DWG\24058\_LS\_PROD.dwg, L1:4 SIGN LANDSCAPE PLAN, 9/11/2025 2:21:41 PM, sheet: 1/1



LANDSCAPE PLAN- SIGN



SCALE SHOWN IS ACCURATE WHEN  
PRINTED ON 22X34 SHEET WITH 1:1  
PLOT SCALE. DOUBLE SCALE ON  
11X17 SHEET WITH 1:2 PLOT SCALE.



100% CD-BID SET

**GATEWAY SIGN AND LANDSCAPING AT EVANS JUNCTION**  
SOUTHWEST CORNER OF 31ST AVE AND HIGHWAY 85

**EVANS COLORADO**  
LANDSCAPE PLAN- SIGN

FILE:	DRAWING HISTORY
24058_LS_PROD.DWG	DATE DESCRIPTION
PROJECT NO: 24058	02/06/2025 100% CD
CAD: TH/JC	09/11/2025 100% CD- BID SET
QUALITY ASSURANCE: KP/JET	







P:\24058\_City\_of\_Evans\_Junction\_Regional\_CAD\_CorridorProduction\_DWG\24058\_LS\_Details.dwg, L2.3 LANDSCAPE DETAILS, 9/11/2025 2:22:28 PM, jones, 1:1

- 2'-8" LENGTH NON-ABRASIVE RUBBER TIES AT 1/3 HEIGHT OF TREE
- (2) 3" DIA LODGE POLE PINE STAKES 1-1/2' FROM TRUNK.
- TOP OF ROOT FLARE 2" ABOVE EXT GRADE. NO SOIL ON ROOT FLARE
- 3" DEPTH MULCH FINISH GRADE
- LOOSENEO SOIL. DIG AND TURN THE SOIL TO REDUCE COMPACTION TO THE AREA TO DEPTH OF ROOT BALL.
- BOTTOM OF ROOT BALL RESTS ON EXT OR RECOMPACTED SOIL
- EXT SOIL
- 3 X DIA ROOT BALL MIN
- NOTES:
1. REMOVE NURSERY STAKES.
  2. PRUNE DEAD OR DAMAGED LIMBS IMMEDIATELY AFTER PLANTING.
  3. REMOVE WIRE TIES AND BURLAP FROM TOP 1/2 OF ROOT BALL.
  4. REMOVE ALL BASKETS.
  5. PRIOR TO MULCHING, LIGHTLY TAMP SOIL AROUND ROOT BALL IN 6" LIFTS TO BRACE TREE. DO NOT OVER COMPACT. WHEN PLANTING PIT HAS BEEN BACKFILLED, POUR WATER AROUND ROOT BALL TO SETTLE THE SOIL.
  6. BACKFILL WITH AMENDED SOIL.
  7. REMOVE STAKES FOLLOWING FIRST GROWING SEASON.
  8. RAKE SUBGRADE AND REMOVE ALL DEBRIS GREATER THAN 1/2" IN DIA. INCLUDING ROCKS, CONCRETE, ORGANIC DEBRIS, AND OR CONSTRUCTION DEBRIS.
  9. PROVIDE SUPPLEMENTAL WATER FOR THE FIRST YEAR FOLLOWING INSTALLATION.


#### 1 CONIFEROUS TREE

N.T.S.

- 2'-8" LENGTH NON-ABRASIVE RUBBER TIES
- (2) 3" DIA LODGE POLE PINE STAKES 1-1/2' FROM TRUNK. STAKE LOCATION SHALL NOT INTERFERE WITH PERMANENT BRANCHES
- TOP OF ROOT FLARE 2" ABOVE EXT GRADE. NO SOIL ON ROOT FLARE
- 3" DEPTH MULCH FINISH GRADE
- LOOSENEO SOIL. DIG AND TURN THE SOIL TO REDUCE COMPACTION TO THE AREA TO DEPTH OF ROOT BALL.
- BOTTOM OF ROOT BALL RESTS ON EXT OR RECOMPACTED SOIL
- EXISTING SOIL
- 3 X DIA ROOT BALL MIN
- NOTES:
1. REMOVE NURSERY STAKES.
  2. PRUNE DEAD OR DAMAGED LIMBS IMMEDIATELY AFTER PLANTING.
  3. REMOVE WIRE TIES AND BURLAP FROM ROOT BALL.
  4. PRIOR TO MULCHING, LIGHTLY TAMP SOIL AROUND ROOT BALL IN 6" LIFTS TO BRACE TREE. DO NOT OVER COMPACT. WHEN PLANTING PIT HAS BEEN BACKFILLED, POUR WATER AROUND ROOT BALL TO SETTLE THE SOIL.
  5. BACKFILL WITH AMENDED SOIL.
  6. REMOVE STAKES FOLLOWING FIRST GROWING SEASON.
  7. RAKE SUBGRADE AND REMOVE ALL DEBRIS GREATER THAN 1/2" IN DIA. INCLUDING ROCKS, CONCRETE, ORGANIC DEBRIS, AND OR CONSTRUCTION DEBRIS.
  8. PROVIDE SUPPLEMENTAL WATER FOR THE FIRST YEAR FOLLOWING INSTALLATION.

#### 2 DECIDUOUS TREE


N.T.S.



- NOTES:
1. FENCE SHALL BE FROM SIGNATURE STONE, 211 30TH ST. GREELEY CO. (970-351-0270)
  2. CONCRETE FENCE IN THE COLOR RAWHIDE.
  3. INSTALL PER MANUFACTURER DETAILS


#### 5 CONCRETE SPLIT RAIL FENCE

N.T.S.



#### 8 ROCK MULCH


N.T.S.



- NOTES:
1. SUBMIT SAMPLE AND SPECIFICATION OF EDGER FOR APPROVAL
  2. EDGER CORNERS SHALL BE BENT TO REQUIRED ANGLE TO FORM CONTINUOUS EDGER. CORNER JOINTS NOT ACCEPTABLE

#### 6 EDGING ALUMINUM

N.T.S.




#### 9 BOULDER PLACEMENT

N.T.S.

#### 3 SHRUB PLANTING


N.T.S.



- NOTES:
1. SHRUBS WITH BROKEN OR CRUMBLING ROOT BALLS WILL BE REJECTED. CONTAINER REMOVAL WILL NOT BE AN EXCUSE FOR DAMAGED ROOT BALLS.
  2. TOP OF MULCH TO BE 1" BELOW ADJ WALKWAY, CURB, EDGING, OR OTHER SURFACE.
  3. PRUNE OUT ALL DAMAGED OR DEAD WOOD.
  4. ALL PLANT MATERIAL TO BE INSPECTED UPON DELIVERY. REJECTED MATERIALS TO BE IMMEDIATELY RETURNED TO SOURCE.
  6. RAKE SUBGRADE AND REMOVE ALL DEBRIS GREATER THAN 1/2" IN DIA. INCLUDING ROCKS, CONCRETE, ORGANIC DEBRIS, AND OR CONSTRUCTION DEBRIS.

#### 4 SEEDING

N.T.S.



- NOTE:
1. SCARIFY SUBGRADE 4", RAKE SUBGRADE AND REMOVE ALL DEBRIS GREATER THAN 1/2" IN DIA. INCLUDING ROCKS, CONCRETE, ORGANIC DEBRIS, AND OR CONSTRUCTION DEBRIS.
  2. LANDSCAPE CONTRACTOR SHALL AMEND SOIL WITH 4 CUBIC YARDS OF ORGANIC COMPOST PER 1,000 SQUARE FEET AND TILL INTO EXISTING TOPSOIL AND PREPARE FOR SEEDING

### 100% CD-BID SET

DRAWING HISTORY	
DATE	DESCRIPTION
02/06/2025	100% CD
09/11/2025	100% CD- BID SET
-	-
-	-
-	-
-	-
-	-
-	-
FILE: 24058_LS_DETAILS.DWG	
PROJECT NO: 24058	
CAD: TH/JC	
QUALITY ASSURANCE: KP/JET	

GATEWAY SIGN AND LANDSCAPING AT EVANS JUNCTION  
SOUTHWEST CORNER OF 31ST AVE AND HIGHWAY 85

EVANS COLORADO  
LANDSCAPE DETAILS

IRRIGATION NOTES

1. THIS SYSTEM DESIGN ASSUMES A MINIMUM DYNAMIC PRESSURE FOR THE IRRIGATION SYSTEM OF 65 PSI, AT A MAXIMUM DISCHARGE OF 30 GPM AT THE 1" POINT-OF-CONNECTION. CONTRACTOR TO VERIFY PRESSURE AND FLOW ON SITE PRIOR TO CONSTRUCTION.
2. THE IRRIGATION SYSTEM POINT-OF-CONNECTION SHALL BE IN THE WATER METER PIT AT SOURCE PROVIDED APPROXIMATE LOCATION SHOWN. INSTALL BACKFLOW PREVENTION/ANTI SIPHON ASSEMBLY PER CITY & STATE BUILDING CODES. VERIFY EXACT LOCATION OF P.O.C. WITH OWNERS REPRESENTATIVE.
3. CONTROLLER AT THE APPROXIMATE LOCATION SHOWN. COORDINATE ELECTRICAL POWER TO THE CONTROLLER WITH THE OWNER'S REPRESENTATIVE. CARE SHOULD BE TAKEN TO INSTALL THE IRRIGATION CONTROLLER IN A LOCATION THAT IS ACCESSIBLE FOR MAINTENANCE. FINAL LOCATION TO BE APPROVED BY OWNERS REPRESENTATIVE.
4. COORDINATE UTILITY LOCATES OF ALL UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION.
5. CONTRACTOR TO COORDINATE PIPE SLEEVING. SLEEVING SHALL BE 3" PVC.
6. DO NOT PROCEED WITH THE INSTALLATION OF THE IRRIGATION SYSTEM WHEN IT IS OBVIOUS IN THE FIELD THAT OBSTRUCTIONS OR GRADE DIFFERENCES EXIST THAT MIGHT NOT HAVE CONSIDERED IN THE DESIGN PROCESS. IF DISCREPANCIES IN CONSTRUCTION DETAILS, LEGEND, NOTES OR SPECIFICATIONS ARE DISCOVERED, BRING ALL SUCH OBSTRUCTIONS OR DISCREPANCIES TO THE ATTENTION OF THE OWNER'S REPRESENTATIVE.
7. DRAWINGS ARE DIAGRAMMATIC. THEREFORE, THE FOLLOWING SHOULD BE NOTED:

A. ALTHOUGH IRRIGATION COMPONENTS MAY BE SHOWN OUTSIDE OF PLANTING AREAS FOR CLARITY, INSTALL IRRIGATION PIPE, WIRING, VALVES, ETC. IN LANDSCAPED AREAS AND WITH PROPERTY LINES.


B. TREE AND SHRUB LOCATION SHOWN ON LANDSCAPE PLANS TAKE PRECEDENCE OVER IRRIGATION EQUIPMENT LOCATIONS. AVOID CONFLICTS BETWEEN THE IRRIGATION SYSTEM, PLANTING MATERIALS, AND ARCHITECTURAL FEATURES.

C. USE ONLY STANDARD TEES AND ELBOW FITTINGS.
7. PROVIDE THE FOLLOWING COMPONENTS TO THE OWNER PRIOR TO THE COMPLETION OF THE PROJECT:

A. TWO (2) OPERATING KEYS FOR EACH TYPE OF MANUALLY OPERATED VALVES AND CONTROLLERS.
8. THE IRRIGATION CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION OF IRRIGATION SLEEVING. SLEEVES ARE REQUIRED FOR BOTH PIPING AND ELECTRICAL WIRING AT EACH HARDSCAPE CROSSING. COORDINATE INSTALLATION OF SLEEVING WITH OTHER TRADES. ANY PIPE OR WIRE WHICH WAS NOT INSTALLED WILL REQUIRE HORIZONTAL BORING BY THE IRRIGATION CONTRACTOR. IRRIGATION CONTRACTOR TO COORDINATE WITH SITE CONTRACTOR FOR TIME OF INSTALLATION AND LOCATION OF ANY SLEEVE AND/OR CONDUIT INSTALLATION.
9. INSTALL ALL ELECTRICAL POWER TO THE IRRIGATION CONTROL SYSTEM IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE AND ALL APPLICABLE LOCAL ELECTRIC UTILITY CODES.
10. INSTALL TWO (2) #14 AWG CONTROL WIRES FROM CONTROLLER LOCATION TO EACH DEAD-END OF MAINLINE FOR USE AS SPARE INCASE OF CONTROL WIRE FAILURE. COIL 3 FEET OF WIRE IN VALVE BOX.
11. ALL PLANT MATERIAL NOT LOCATED IN LAWN AREAS SHALL BE DRIP IRRIGATED BY AUTOMATIC CONTROLLED SYSTEM. RAINBIRD EQUIPMENT OR EQUAL. A COMPLETE LIST OF EQUIPMENT, SHOP DRAWING CATALOG CUTS, LAYOUT PERFORMANCE AND MAINTENANCE WARRANTY INFORMATION SHALL BE SUBMITTED TO THE OWNERS REPRESENTATIVE FOR APPROVAL PRIOR TO COMMENCING WORK. SAID INFORMATION SHALL BE COMPILED ALONG WITH AS-BUILT DRAWINGS AND MAINTENANCE INSTRUCTION AND SUBMITTED TO OWNER'S REPRESENTATIVE FOR APPROVAL AT FINAL COMPLETION. CONTRACTOR SHALL DEMONSTRATE COMPLETE OPERATING SYSTEM AND MAINTENANCE TO OWNER'S REPRESENTATIVE AND OWNER'S MAINTENANCE AND OPERATING PERSONNEL.
12. CONTRACTOR SHALL BE REQUIRED TO START UP AND WINTERIZE SYSTEM FOR THE WARRANTY PERIOD, ONE YEAR FROM FINAL COMPLETION, AND MAKE ALL ADJUSTMENTS AND REPAIRS REQUIRED TO INSURE EFFICIENT OPERATION.
13. CONTRACTOR SHALL PROVIDE ALL REQUIRED IRRIGATION WATER CONTROL, FILTRATION PRESSURE REGULATION, WASTE AND DRAINAGE REQUIREMENTS OF A COMPLETE MAINTENANCE SYSTEM.
14. CONTRACTOR SHALL PROVIDE 3 EACH 2 G.P.H. EMITTERS TO EACH TREE, 2 EACH 1 G.P.H. EMITTERS TO EACH SHRUB, VINE OR HERBACEOUS PLANT. ALL EQUIPMENT SHALL BE CONCEALED OR OTHERWISE PROTECTED UNDER SPECIFIED MULCHES AND IN VALVE BOXES WHERE ACCESS IS REQUIRED.
15. ALL VALVE BOXES SHALL BE STAMPED WITH IDENTIFICATION INFORMATION.

IRRIGATION SCHEDULE

SYMBOL	MANUFACTURER/MODEL/DESCRIPTION	QTY	PSI	GPM	RADIUS
	RAIN BIRD 5006-PC 1.5 TURF ROTOR, 6IN. POP-UP, PLASTIC RISER. ADJUSTABLE TO FULL CIRCLE. STANDARD ANGLE NOZZLE.	49	25	1.12	33'
	RAIN BIRD 5006-PC 2.0 TURF ROTOR, 6IN. POP-UP, PLASTIC RISER. ADJUSTABLE TO FULL CIRCLE. STANDARD ANGLE NOZZLE.	13	25	1.5	35'
SYMBOL	MANUFACTURER/MODEL/DESCRIPTION	QTY			
	RAIN BIRD XCZ-100-PRF MEDIUM FLOW DRIP CONTROL KIT, 11N. DV VALVE, 11N. PRESSURE REGULATING FILTER, 40PSI PRESSURE REGULATOR. 5 GPM-20 GPM.	6			
	RAIN BIRD XFCV-06-12 DRIP RING	28			
	AREA TO RECEIVE DRIP EMITTERS RAIN BIRD XBCV-PC SINGLE OUTLET, PRESSURE COMPENSATING DRIP EMITTERS. FLOW RATES OF 0.5 GPH=BLUE, 1.0 GPH=BLACK, AND 2.0 GPH=RED. COMES WITH A SELF-PIERCING BARB INLET X BARB OUTLET. WITH CHECK VALVE.	9,476 SF			
	Emitter Notes: 10PC emitters (2 assigned to each 1 GAL. plant)	242			
	20PC emitters (2 assigned to each 5 GAL. plant)	232			
SYMBOL	MANUFACTURER/MODEL/DESCRIPTION	QTY			
	RAIN BIRD PEB-PRS-D 11N., 1-1/2IN., 2IN., 3IN. PLASTIC INDUSTRIAL REMOTE CONTROL VALVE. LOW FLOW OPERATING CAPABILITY, GLOBE CONFIGURATION. WITH PRESSURE REGULATOR MODULE.	5			
	FEBCO 825YA 1-1/2" REDUCED PRESSURE BACKFLOW PREVENTER	1			
	BASELINE BL-3200P-R24 24-STATION CONVENTIONAL WIRE CONTROLLER IN 16-GAUGE STAINLESS-STEEL PEDESTAL ENCLOSURE, EXPANDABLE TO 200 STATIONS.	1			
	RAIN BIRD WR2-RC WIRELESS RAIN SENSOR COMBO, INCLUDES 1 RECEIVER AND 1 RAIN SENSOR TRANSMITTER.	1			
	RAIN BIRD FS-150-B 1-1/2IN. FLOW SENSOR, BRASS MODEL. SUGGESTED OPERATING RANGE 4.0 GPM TO 80.0 GPM. SIZE FOR FLOW NOT ACCORDING TO PIPE SIZE. RAIN BIRD COMPATIBLE CONTROLLERS: ESP-LXIVM(P)   LX D   LXME2(P)   ME3, OR CONTROLLERS ACCEPTING CUSTOM K-FACTOR AND OFFSET. INSTALL IN RAIN BIRD VALVE BOX.	1			
	POINT OF CONNECTION	1			
	IRRIGATION LATERAL LINE: PVC CLASS 200 SDR 21	3,024 LF			
	IRRIGATION MAINLINE: PVC SCHEDULE 40	515.9 LF			
	PIPE SLEEVE: PVC SCHEDULE 40	70.5 LF			



VALVE SCHEDULE

NUMBER	MODEL	SIZE	TYPE	GPM	DESIGN PSI	PSI	PSI @ POC	PRECIP
1	RAIN BIRD PEB-PRS-D	1"	TURF ROTOR	11.2	25	27.5	34.3	0.48 in/h
2	RAIN BIRD XCZ-100-PRF	1"	AREA FOR DRIP EMITTERS	1.35	10	15.0	15.2	0.31 in/h
3	RAIN BIRD XCZ-100-PRF	1"	DRIP RING	0.18	20	25.0	25	0.44 in/h
4	RAIN BIRD PEB-PRS-D	1"	TURF ROTOR	13.44	25	28.6	33.1	0.33 in/h
5	RAIN BIRD PEB-PRS-D	1"	TURF ROTOR	14.56	25	28.1	31.1	0.33 in/h
6	RAIN BIRD XCZ-100-PRF	1"	AREA FOR DRIP EMITTERS	3.26	10	15.1	15.2	0.25 in/h
7	RAIN BIRD XCZ-100-PRF	1"	DRIP RING	1.08	20	25.0	25.0	0.44 in/h
8	RAIN BIRD PEB-PRS-D	1"	TURF ROTOR	15.68	25	28.7	29.0	0.43 in/h
9	RAIN BIRD XCZ-100-PRF	1"	DRIP RING	1.26	20	25.1	25.1	0.44 in/h
10	RAIN BIRD XCZ-100-PRF	1"	AREA FOR DRIP EMITTERS	4.42	10	15.1	15.4	0.23 in/h
11	RAIN BIRD PEB-PRS-D	1"	TURF ROTOR	19.5	25	31.4	34.4	0.29 in/h

CRITICAL ANALYSIS

P.O.C. NUMBER: 01  
Water Source Information:

FLOW AVAILABLE  
Custom Max Flow: 30 GPM  
Flow Available 30 GPM

PRESSURE AVAILABLE  
Static Pressure at POC: 65 PSI  
Pressure Available: 65 PSI

DESIGN ANALYSIS  
Maximum Station Flow: 19.5 GPM  
Flow Available at POC: 30 GPM  
Residual Flow Available: 10.5 GPM

Critical Station: 11  
Design Pressure: 25 PSI  
Friction Loss: 3.19 PSI  
Fittings Loss: 0.32 PSI  
Elevation Loss: 0 PSI  
Loss through Valve: 2.85 PSI  
Pressure Req. at Critical Station: 31.4 PSI  
Loss for Fittings: 0.28 PSI  
Loss for Main Line: 2.81 PSI  
Loss for POC to Valve Elevation: 0 PSI  
Loss for Backflow: 0 PSI  
Critical Station Pressure at POC: 34.4 PSI  
Pressure Available: 65 PSI  
Residual Pressure Available: 30.6 PSI

WATERING SCHEDULE

NUMBER	MODEL	TYPE	PRECIP	IN./WEEK	MIN./WEEK	GAL./WEEK	GAL./DAY
1	RAIN BIRD PEB-PRS-D	TURF ROTOR	0.48 in/h	1	125	1,400	467
2	RAIN BIRD XCZ-100-PRF	AREA FOR DRIP EMITTERS	0.31 in/h	1	196	265	132
3	RAIN BIRD XCZ-100-PRF	DRIP RING	0.44 in/h	1	136	24.5	8.16
4	RAIN BIRD PEB-PRS-D	TURF ROTOR	0.33 in/h	1	181	2,433	811
5	RAIN BIRD PEB-PRS-D	TURF ROTOR	0.33 in/h	1	182	2,650	883
6	RAIN BIRD XCZ-100-PRF	AREA FOR DRIP EMITTERS	0.25 in/h	1	244	794	397
7	RAIN BIRD XCZ-100-PRF	DRIP RING	0.44 in/h	1	136	147	49.0
8	RAIN BIRD PEB-PRS-D	TURF ROTOR	0.43 in/h	1	139	2,180	727
9	RAIN BIRD XCZ-100-PRF	DRIP RING	0.44 in/h	1	136	171	57.1
10	RAIN BIRD XCZ-100-PRF	AREA FOR DRIP EMITTERS	0.23 in/h	1	266	1,176	588
11	RAIN BIRD PEB-PRS-D	TURF ROTOR	0.29 in/h	1	206	4,017	1,339
TOTALS:					1,947	15,257	5,458

100% CD-BID SET

GATEWAY SIGN AND LANDSCAPING AT EVANS JUNCTION

SOUTHWEST CORNER OF 31ST AVE AND HIGHWAY 85


EVANS COLORADO

IRRIGATION SCHEDULE & NOTES



DRAWING HISTORY	
DATE	DESCRIPTION
02/06/2025	100% CD
09/11/2025	100% CD- BID SET
-	-
-	-
-	-
-	-
-	-
-	-
-	-
-	-

FILE:	24058_IR_PROD.DWG
PROJECT NO:	24058
CAD:	TH/JC
QUALITY ASSURANCE:	KPJ/ET



SCALE SHOWN IS ACCURATE WHEN  
PRINTED ON 22X34 SHEET WITH 1:1  
PLOT SCALE. DOUBLE SCALE ON  
11X17 SHEET WITH 1:2 PLOT SCALE.

— POINT OF CONNECTION TO BE AT WATER METER PIT. CONTRACTOR TO COORDINATE POWER FOR CONTROLLER AND EXACT LOCATION OF POINT OF CONNECTION AND CONTROLLER.

**GATEWAY SIGN AND LANDSCAPING AT EVANS JUNCTION**  
SOUTHWEST CORNER OF 31ST AVE AND HIGHWAY 85

EVANS COLORADO  
IRRIGATION PLAN-NORTH

<b>FILE:</b>	24058_IR_PROD.DWG					
<b>PROJECT NO:</b>	24058					
<b>CAD:</b>	THJC					
<b>QUALITY ASSURANCE:</b>	K9/JET					
<b>DRAWING HISTORY</b>	<b>DATE</b>	<b>DESCRIPTION</b>				
	02/06/2025	100% CD	-	-	-	-
	09/11/2025	100% CD- BID SET	-	-	-	-
	-	-	-	-	-	-
	-	-	-	-	-	-
	-	-	-	-	-	-
	-	-	-	-	-	-



P:\24058\_Evans\_Colorado\_Retail\CADD\_CAD\PRODUCTION\_DWG\24058\_IR\_PROD.dwg, L3.3 IRRIGATION PLAN SOUTH, 9/11/2025 2:23:09 PM, jared, 1:1




## IRRIGATION PLAN-SOUTH



SCALE: 1" = 20'

SCALE SHOWN IS ACCURATE WHEN  
PRINTED ON 22X34 SHEET WITH 1:1  
PLOT SCALE. DOUBLE SCALE ON  
11X17 SHEET WITH 1:2 PLOT SCALE.



9 1.26  
1" 1"  
10 4.42  
1" 1"  
11 19.5  
1" 1"

7 1.08  
1" 1"  
8 15.7  
1" 1"

POINT OF CONNECTION TO BE AT WATER METER PIT. CONTRACTOR TO COORDINATE POWER FOR CONTROLLER AND EXACT LOCATION OF POINT OF CONNECTION AND CONTROLLER.

BACKFLOW DEVICE SHALL BE LOCATED INSIDE A GREEN STRONG BOX

## 100% CD-BID SET

**GATEWAY SIGN AND LANDSCAPING AT EVANS JUNCTION**  
SOUTHWEST CORNER OF 31ST AVE AND HIGHWAY 85

EVANS COLORADO  
IRRIGATION PLAN-SOUTH



DRAWING HISTORY	
DATE	DESCRIPTION
02/06/2025	100% CD
09/11/2025	100% CD- BID SET
-	-
-	-
-	-
-	-
-	-
-	-
FILE: 24058_IR_PROD.DWG	
PROJECT NO: 24058	
CAD: TH/JC	
QUALITY ASSURANCE: KP/JET	

